

What the Commission’s Conditions Actually Say: a census of condition text, and the object it describes

Dan Post

September 2026

Abstract

The conditions memo established that the Commission’s conditions of approval live in its motions, not in its minutes, and probed 20 cases a year for them against one URL pattern per host. This memo replaces that sample with a census — every case and every motion number the item table records, probed against every place the department has published a motion — and then reads what the conditions say, before any coding scheme is imposed on them.

Condition text reaches back further than the conditions memo said, but not far. The probe answered 127,920 candidate URLs and found 10,165 documents. Parsed condition text now exists for 1,952 of the 4,048 items the item table flags as conditioned (48.2%); the earliest of those items was heard in 1999, and the oldest motion read dates from 1984. The conditions memo put the boundary at 2010; the sources that reach before it are the old site’s document modules and FTP tree, the pre-2003 city pages kept by the Wayback Machine, and adopted motions attached to later packets. They reach 2.4% of conditioned items heard in 1998–2002 and 7.6% in 2003–2009, against 78.9% in 2011–2014. The pre-2010 residual is overwhelmingly items for which no document was found at any address: 1,586 of 1,600.

The conditions are a template with a thin project-specific layer. 1,383 distinct condition headings occur across the motions read; the 40 most frequent carry 76.2% of all headed conditions, and 642 occur in one motion only. What varies from project to project is numbers — hours, feet, periods, unit counts — and a short tail of conditions written for the site.

The entitlement’s maturity is written into the template. The validity condition states a period on 98% of the motions that carry one, and on 96% of those the period is 36 months. The extension condition states a period on only 32 of the 3,488 motions that carry one: it extends the clock by the length of a delay caused by an agency, an appeal or a lawsuit.

Contents

1	Coverage: a census, replacing the conditions memo's sample	3
1.1	What was searched	3
1.2	The census	7
1.3	What was read, and the earliest year by source	7
1.4	How well the text is read	12
2	Anatomy of one motion	14
3	Every standing section, and the most frequent headings	16
4	The long tail	48
5	Counts as a variable	51
6	Draft against adopted	54
7	The conditions that set the clock	57
8	The conditions memo's coding scheme on the full set	59
9	The numbers inside the conditions	60
10	Recorded Notices of Special Restrictions	62
11	Established, and not established	62
12	Reproducing this	63
A	Data dictionary for conditions_long	64

1 Coverage: a census, replacing the conditions memo’s sample

The universe. A case is a distinct case number after upper-casing, stripping white space and expanding a two-digit year against the hearing year; the function that says so (`case_universe` in `acquire_external_data.py`) is the one every memo now imports. The item table holds 8,958 such cases. The corpus and conditions memos counted 8,987, because they counted printed strings, and 29 cases were printed both ways — `99.530C` at one hearing and `1999.530C` at another. The census probes the 8,958, and every case count below is on that basis.

1.1 What was searched

The conditions memo’s Table 4 asked whether a packet existed for 20 sampled cases a year at two constructed addresses (578 cases, 225 packets found). Four things found while building the census changed the search, and each became a stage of it.

- **No directory lists its contents.** 0 of the 10 directory and bucket-listing URLs tried returned an index, so every document has to be asked for by name.
- **The minutes link their own documents.** The HTML minutes hyperlink motions and packets on the old `sf-planning.org` tree (the links run from 2000 to 2017), and from 2017 the PDF minutes link every motion, resolution and DRA number to the adopted document in the department’s vault. Reading the raw corpus locally gave 12,917 links from 650 minutes documents. Many of the archived HTML pages disable their links by renaming the attribute to `data-href`; reading `href` alone had silently dropped every one.
- **The archived agendas link the packets.** A crawl of 247 archived agenda pages of the old site found 2,127 document links, and the 2015–2026 hearing pages (315 of them) 4,007 more.
- **The Wayback Machine holds the pre-2003 city site.** The CDX index returned 92,055 URLs captured with status 200 under the 11 prefixes searched (Table 2). Almost all are agendas, notices and reports. The ones named by motion or case are few: 20 HTML motion pages from the pre-2003 city site, 136 motion PDFs and 2,963 packets, the motion captures from 2002 and the packets from 2011. That is the Wayback yield, reported by year as the brief asks, and it is small.

Together the four sources gave 11,527 distinct URLs, 8,932 of them about a case or a motion. The probe then asked for every case in the universe under every case-keyed family — as printed, as its stem, and as the stem with each suffix the minutes attach to it — and for every motion and resolution number under the motion families, in the hearing year and the years either side. Table 1 lists the families. It used `HEAD`, falling back to a ranged `GET` where `HEAD` was refused, at no more than 2 requests a second per host. It answered 127,920 URLs: 10,165 documents, 117,472 absent, 275 behind the vault’s sign-in page or its “not public” error page, 8 redirected by a dead host to its new home page (counted as absent, not as documents), and 0 other. The probe finished.

Table 1: The URL families probed. ‘Constructed’ families were probed for every case or motion number the item table records; the others are exact URLs found in the minutes’ own hyperlinks, on the hearing pages, on the archived agenda pages or in the Wayback Machine’s index. Column labels are the ones Table 4 uses.

Label	Holds	Where
A-yr	adopted	<code>commissions.sfplanning.org/cpcmotions/<year>/<motion>.pdf</code>
A-yr-m	adopted	the same keys on the S3 mirror, <code>default.sfplanning.org/meetingarchive/planning_dept/commissions.sfplanning.org/cpcmotions/...</code>
A-ftp	adopted	the old site’s FTP tree on the mirror, <code>.../sf-planning.org/ftp/files/Commission/cpcmotions/<motion>.pdf</code>
A-mod	adopted	the old site’s document modules, <code>.../sf-planning.org/modules/<motion>-documentid=<n>.pdf</code> , linked from the archived agenda and minutes pages
A-html	adopted	the pre-2003 city site’s HTML motion pages, <code>ci.sf.ca.us/planning/f_motion/<motion>.htm</code> ; Wayback captures only the same, on <code>sfgov.org/planning/cpcmot/</code> ; Wayback captures only
A-vault	adopted	the department’s document vault, <code>citypln-m-extnl.sfgov.org/External/link.ashx?... and SharedLinks.aspx?...</code> , linked from the 2017– minutes
P	draft	<code>commissions.sfplanning.org/cpcpackets/<case>.pdf</code>
P-m	draft	the same keys on the S3 mirror
P-ftp	draft	the old site’s FTP tree, <code>.../ftp/files/Commission/cpcpackets/<case>.pdf</code> , live and in Wayback captures
P-date	draft	<code>citypln-m-extnl.sfgov.org/Commissions/CPC/<M>_<D>_<YYYY>/Commission%20Packet/<case>.pdf</code> , keyed by hearing date
DRA	DR action	<code>commissions.sfplanning.org/cpcdra/</code> , its mirror and the old FTP tree

Table 3 records the searches that came back empty or closed, so that nobody runs them again.

Table 2: The Wayback Machine’s yield: distinct document URLs captured with status 200 under the 11 CDX prefixes, by the year of first capture and by kind. Adopted motions are HTML pages (pre-2003 city site) or PDFs named by motion number; packets are PDFs named by case. Everything else captured under the prefixes — agendas, notices, reports, and the old site’s **ShowDocument** pages, whose URLs name no motion or case — is in ‘other’. A motion or packet capture’s live equivalent is probed; a capture is pulled only where the live copy is gone.

First captured	motion (HTML)	motion (PDF)	packet (PDF)	DRA	other	All
1999	0	0	0	0	93	93
2000	0	0	0	0	72	72
2001	0	0	0	0	513	513
2002	18	0	0	0	915	933
2003	2	0	0	0	1,531	1,533
2004	0	0	0	0	907	907
2005	0	0	0	0	233	233
2006	0	0	0	0	410	410
2007	0	0	0	0	817	817
2008	0	0	0	0	10,169	10,169
2009	0	0	0	0	68,365	68,365
2010	0	0	0	0	2,282	2,282
2011	0	3	34	0	1,113	1,150
2012	0	129	304	25	1,134	1,592
2013	0	1	26	0	132	159
2014	0	0	44	0	58	102
2015	0	0	43	0	57	100
2016	0	0	22	0	16	38
2017	0	0	46	0	16	62
2018	0	0	94	0	26	120
2019	0	0	36	0	3	39
2020	0	0	68	0	0	68
2021	0	0	243	0	0	243
2022	0	0	1,332	0	0	1,332
2023	0	1	85	0	0	86
2024	0	2	452	0	1	455
2025	0	0	126	0	0	126
2026	0	0	8	0	0	8
All	20	136	2,963	25	88,863	92,007

Table 3: Negative results: searches that came back empty or closed, so nobody runs them again.

Search	What was tried	Result
Directory listings	10 directory and S3 bucket-listing URLs on both hosts	0 returned an index; every document has to be asked for by name
Adopted motions by year on <code>commissions.sfplanning.org</code>	19,811 constructed URLs	915 answered; the same keys on the S3 mirror answered 477
Date-keyed packet host before 2022	30,096 constructed URLs for hearings before 2022	0 answered
Vault links as the 2017–2021 minutes print them	the staff form <code>/link.ashx</code>	a sign-in page; the public form <code>/External/link.ashx</code> serves the same object
Vault objects not shared publicly	275 links	the vault’s sign-in or “not public” page; counted as absent, not as documents
The pre-2003 city site’s motion pages	Wayback CDX under <code>ci.sf.ca.us/planning</code> and <code>sfgov.org/planning</code>	20 motion pages captured in all
The city site’s later planning pages	Wayback CDX under <code>sfgov.org/site/planning</code> and <code>sfgov.org/site/uploadedfiles/planning</code>	82,581 captures, 0 named by a motion or case number
Recorded Notices of Special Restrictions	the Assessor-Recorder’s public pages (read, not searched)	an index by APN and document type from 1990; images by purchase; bulk access not addressed (§10)

1.2 The census

Table 4 is the census, by the first hearing year of the case or motion each document belongs to and by URL family; Figure 1 shows what it yielded, year by year — the motions read and the share of the conditioned docket they reach. The census is what the conditions memo’s Table 4 becomes when every case is asked about, and it replaces it. Each family answers for its own span of years: the old site’s document modules and FTP tree for the last years of the HTML minutes, the motion archive for the first PDF years, the vault from the first minutes that link it, the date-keyed packet host for the most recent hearings, and the main packet host across most of the PDF era beside them. A case first heard early can still have a packet if it came back to the Commission later, which is why the packet columns reach back before the host existed. For cases first heard before the old site’s span almost nothing answers at a live address: the pre-2003 motions survive only as Wayback captures and as exhibits to later packets.

1.3 What was read, and the earliest year by source

A document found is not a result; a document read is. Table 5 counts motion sections with at least one parsed condition, one copy of each motion whichever address reached it — the same adopted motion arrives as a standalone file, a mirror copy and an exhibit to a later packet — by source and era. **The answer to the question the census was built for is its last column:** the earliest hearing year for which condition text is retrievable, by source.

- Adopted motions: the old site’s FTP tree from 2009, its document modules from 2007, the

Table 4: The census: URLs answering with a document, by the first hearing year of the case or motion each belongs to and by URL family (Table 1). A document reached at two addresses — a mirror — is counted at each. ‘A’ columns are adopted motions, ‘P’ columns packets (draft motions), ‘DRA’ Discretionary Review Actions, which are counted and not pulled.

Year	A-yr	A-yr-m	A-ftp	A-mod	A-vault	P	P-m	P-ftp	P-date	DRA	All
2001						1					1
2003						1	1			1	3
2007						2	2				4
2008				132		2	1		1		136
2009				1		7	3	5			16
2010			129			38	39	142		15	363
2011	191	40				296	341	18		14	900
2012	145	144	1			251	303	122		15	981
2013	442	169				277	305	5			1,198
2014	137	124				247	290	14			812
2015					1	205	1		3		210
2016						252			3		255
2017					16	291	2		1		310
2018					324	398	1	2	6		731
2019					271	378			10		659
2020					230	291			24		545
2021					248	282			50		580
2022					139	266			277		682
2023					286	10			346		642
2024					207	108			236		551
2025					215	5			231		451
2026					36				89		125
undated							4		6		10
All	915	477	130	133	1,973	3,608	1,293	308	1,283	45	10,165




Figure 1: Top: the share of items the item table flags as conditioned for which some condition text has now been parsed, by hearing year. Bottom: the motion sections with parsed conditions behind it, adopted and draft, by hearing year.

department’s vault from 2017, and the pre-2003 city pages (through the Wayback Machine) from 2001.

- Draft motions in packets: from 2007.
- Adopted motions embedded in later packets: from 1984. A motion that modifies an earlier approval attaches the original, so an old motion survives inside a new packet. The oldest of these predate the corpus and belong to no case in it: 450 motion sections read belong to no case in the universe at all. The earliest motion read for a case in the universe was heard in 1999. Measured on the item table instead, the earliest conditioned item that now has condition text was heard in 1999.

Correction (2026-09-11). The previous version said that “the earliest motion read for a case in the universe was heard in 1994, years before the case came back to the Commission”. No such motion was read. The document is the packet for case 2019-012888CUA, with two earlier adopted motions bound into it: Motion 13693 of May 26, 1994 (case 94.160C), and Motion 18915 of July 11, 2013 (case 2013.0023C), a restaurant next door. The older motion is a scan whose running header repeats “CITY PLANNING COMMISSION / MOTION NO.” on every page, so every page read as a title page, and the rule that folds a title block spilling onto a second page into one section folded the later motion into the older one: its conditions were filed under the older motion’s date and, because the later case number is printed on more pages, under the later case. The parser now opens a new section at a title page that carries a different motion number (round 3, §1.4). Every year-span that rested on it moves: Tables 11 and 12 no longer begin at 1994, and the earliest motion read for a case in the universe is now 1999.

Table 5: Condition text actually read: motions (adopted) and draft motions (in packets) with at least one parsed condition, by source and hearing year. One copy of each motion is counted, whichever source reached it first in the canonical order.

Type	Source	1998–2002	2003–2009	2010	2011–2014	2015–2017	2018–2021	2022–2026	undated	Earliest
adopted	adopted motions, the old site’s FTP tree	0	1	81	0	0	0	0	0	2009
	adopted motions, commissions.sfplanning.org (by year)	0	1	0	154	0	0	0	0	2007
	adopted motions, the S3 mirror of the same	0	0	0	315	0	0	0	0	2011
	adopted motions embedded in a later packet (2 via Wayback)	26	18	25	11	30	4	15	1	1984
	adopted motions, pre-2003 city pages (Wayback)	6	0	0	0	0	0	0	0	2001
	adopted motions, the department vault	0	0	0	0	11	554	471	0	2017
	adopted motions, the old site’s document modules	0	71	0	0	0	0	0	0	2007
draft	packets, citypln (by hearing date)	0	0	1	0	0	0	592	0	2010
	packets, commissions.sfplanning.org	0	2	0	86	390	683	1	22	2007
	packets, the old site’s FTP tree (10 via Wayback)	0	1	103	7	4	0	0	2	2009
	packets, the S3 mirror	0	0	8	472	0	0	0	5	2010
	adopted motions, the department vault	0	0	0	0	0	6	0	0	2021
All		32	94	218	1,045	435	1,247	1,079	30	1984

How much of the conditioned docket has text. Table 6 crosses the parsed sections with the item table. 1,952 of the 4,048 conditioned items (48.2%) now have some condition text, draft or adopted — 2.4% of those heard in 1998–2002, 7.6% in 2003–2009, 71.6% in 2010, 78.9% in 2011–2014, 63.8% in 2015–2017, 83.2% in 2018–2021 and 84.0% in 2022–2026.

The residual, named. Table 7 sorts the 2,096 conditioned items without text by why. For 380 a document keyed to the item was found and read and yielded no conditions — a staff report, a Discretionary Review Action, a motion that attaches none. For 15 a document was found and not read: over the size cap, a failed download, or a DRA, which the census counts and does not pull.

Table 6: How much of the conditioned docket now has condition text. ‘Conditioned’ is the item table’s `conditions_imposed` flag. An item has condition text when a parsed motion section with at least one condition is keyed to its case, or is the adopted motion whose number the item records.

Hearing years	Conditioned items	With condition text	Share	Motion number, no text
1998–2002	626	15	2.4%	401
2003–2009	1,070	81	7.6%	644
2010	134	96	71.6%	28
2011–2014	679	536	78.9%	127
2015–2017	312	199	63.8%	86
2018–2021	713	593	83.2%	112
2022–2026	514	432	84.0%	78
All	4,048	1,952	48.2%	1,476

For 1,118 the item records a motion number and no document answered at any address; for 583 it records none, so only the case-keyed families could find it. Before 2010 the residual is almost entirely the last two kinds: 1,586 of the 1,600 pre-2010 conditioned items without text had no document at any address. More work on the parser will not move them; a records request might.

Table 7: The residual: conditioned items with no condition text, by why. ‘Found’ means some probed or discovered URL keyed to the item’s case or motion number answered with a document; ‘read’, that the pull opened it. A document found and read that yields no conditions is usually a staff report or a Discretionary Review Action rather than a motion; one found and not read is over the size cap, failed, or a DRA, which is not pulled.

Hearing years	No text	Found, read	Found, not read	None found, number	None found, no number
1998–2002	611	5	0	396	210
2003–2009	989	7	2	636	344
2010	38	18	2	10	8
2011–2014	143	124	1	14	4
2015–2017	113	68	0	37	8
2018–2021	120	92	8	15	5
2022–2026	82	66	2	10	4
All	2,096	380	15	1,118	583

Mention rate beside parse rate. A change of format looks like missing data unless the rate at which the documents *mention* the thing is measured beside the rate at which it is *parsed*. Table 8 does that over the 5,860 motion sections read. 4,596 mention an Exhibit A; 4,186 have one located and parsed (a located Exhibit A yields at least one parsed condition in all but 6 of them, which is why the table carries one column for the two), and 91 have an “Exhibit A” that is some other attachment — a draft ordinance, a development agreement, the department’s response to a CEQA appeal, a mitigation-monitoring table — which the parser now recognises and declines. The remaining 337 mention an Exhibit A that was neither located nor rejected. Reading a sample

of them finds three kinds: sections that mention another document’s Exhibit A in running text (the ordinance, agreement or mitigation program a resolution adopts), files that end before their Exhibit A, and parser misses. The validation below is what measures the last.

Table 8: Mention rate beside parse rate, over every motion section read (one copy of each). A section that mentions an Exhibit A but has none located is either a motion that attaches no conditions and says so, one whose Exhibit A is another kind of attachment (rejected: a draft resolution, an agreement, a mitigation table), or a parser miss; the last is what the validation measures. ‘Located’ is an Exhibit A heading found and accepted as conditions; every line after it becomes at least one row, so a located Exhibit A yields a parsed condition in all but 6 sections, and the count of sections with a condition is not shown as a column of its own.

Hearing years	Sections	Mention Exhibit A	Exhibit A rejected	Exhibit A located
1998–2002	39	35	0	33
2003–2009	166	114	2	95
2010	305	250	6	218
2011–2014	1,500	1,141	24	1,045
2015–2017	608	483	19	435
2018–2021	1,697	1,370	27	1,248
2022–2026	1,478	1,162	11	1,081
undated	67	41	2	31
All	5,860	4,596	91	4,186

1.4 How well the text is read

The parsing rules live in `condition_parser.py`, apart from the orchestration, so they could be hashed and frozen. 20 documents spanning the eras and formats were drawn once, with a fixed seed, stratified on era and container, and including documents with no conditions, so that a detector finding conditions where there are none would show. The rules were frozen (2026-09-11 02:30) *before* any label was written, and the documents were then labelled condition by condition from the source layout, by readers who never saw the parser’s output: 395 conditions, after 1 label was changed on checking the source (a compliance line the source had numbered as if it were a condition; the decision is kept in `gold_adjudications.csv`).

- **Round 1, the rules as first frozen:** the parser’s rows matched the labelled boundaries with a precision of 85.1% and a recall of 76.5%. The misses were systematic, not scattered: numbers printed as separate text objects beside their lines, nested numbering in the 1998–2010 motions (lettered parts holding parenthesised conditions), numbering that restarts or jumps, compliance lines that begin mid-line, and page headers that scanned and HTML copies keep inside the text.
- **Round 2:** each of those was fixed and the rules frozen again (2026-09-11 03:07). On the same documents the precision was 97.7% and the recall 98.0% (in-sample). Out of sample, 30 canonical rows drawn at random after that freeze, from documents pulled after it, were checked against the source pages: 29 of 30 started and ended where the condition does.
- **Round 3, the rules as used:** this memo’s own tables showed round 2 running one condition into the next — “Sidewalk Maintenance” holding “10. Community Liaison”, a “Conformity

with Current Law” that stated “60 percent”, a “Lighting” condition that stated a period of “107 years” (the age of a cottage, in a neighbour’s letter bound after the draft motion), and the 1994 date corrected above. The round-2 checks had not caught it because a section read as one block is one row however many conditions it holds, and a row drawn at random rarely lands on it. Six boundary rules were added, each written against a failure a corpus-wide detector found, never against the gold labels (the gold documents were not opened): a title page with a different motion number opens a new section; a letter ends an Exhibit A; a numbered list inside one condition (the transformer-vault schedule) no longer makes the 2011–2014 bold-named template “numbered”; the numbering margin follows the page on a shifted scan; in a numbered section, prose opening with a name after a closed compliance line is a condition whose number the scan lost; and a garbled footer is not a section head. Table 9 counts what they changed over the whole parse. The rules were frozen again (2026-09-11 19:33). On the gold documents the precision is 98.2% and the recall 98.5%; the heading matches the label on 100.0% of the 240 matched rows that carry one, and in the 2 gold documents with no conditions the parser found 0. **These are in-sample figures:** the gold documents belong to the pool the rules were written against. Of the 30 rows round 2 was checked on out of sample, round 3 reproduces 30 exactly, 29 of them correct: round 2’s out-of-sample figure stands for round 3 on those rows.

- **Out of sample, round 3:** 30 canonical rows drawn at random, after the third freeze, from 9 documents outside the gold set that were pulled after it — documents no rule was written against — and checked against the source pages. 96.7% start and end where the condition does (100.0% start correctly, 96.7% end correctly), and the heading is right on 100.0% of the 30 that have one. **These are the figures to quote**, with one qualification: the documents pulled after the third freeze are the last of the pull — the largest packets — and the rows drawn from them were all heard between 2016 and 2025, in the modern template, so this sample says nothing about the older formats; for those, round 2’s check, which round 3 reproduces row for row, is the out-of-sample evidence.

Table 9: What round 3’s boundary rules changed. Each quantity is computed the same way on round 2’s whole parse (archived at its close) and on this one, over the 5,644 documents both read; the 23 documents pulled after round 2 closed are left out of both columns. The last three rows are the merge detectors the round was written against (the second also counts real sub-parts that carry a name, so its level is not an error count). Nothing here is a validation score; those are in the text.

Quantity	Round 2	Round 3
condition rows (one copy of each motion)	84,684	86,385
motion sections read	5,826	5,827
with an Exhibit A located	4,173	4,173
with at least one condition	4,170	4,167
standing blocks and unsplit sections (implicit rows)	22,285	21,050
distinct condition headings	1,212	1,381
median conditions per adopted motion	14	14
earliest year of a motion read for a case in the universe	1994	1999
bodies holding the next condition’s number and name	31	16
bodies holding another frequent heading as a name	1,008	413
bodies holding a letter’s salutation or “Re:” line	34	1

2 Anatomy of one motion

Table 10 walks one conditional-use motion end to end: Motion No. 19244, case 2014.0270C, adopted 2014-09-18, 16 pages ([source](#)). It is chosen by rule rather than by taste — the born-digital adopted conditional-use motion in the modern template with the median number of conditions — so it is the typical case, not the interesting one.

The motion has two halves, and only the second is conditions. The first is the Commission’s reasoning: a title block, a preamble reciting the application and the environmental determination, and findings. Two of the findings carry the discretion. Under Planning Code §303 the Commission finds that the use is necessary or desirable and compatible with the neighbourhood; under §101.1 it finds the project consistent with the priority policies. The decision paragraph then approves the application subject to the conditions attached as Exhibit A and in general conformance with the plans on file stamped Exhibit B, and the Commission secretary certifies the vote.

The second half is Exhibit A. It opens with standing blocks that are not conditions of the project but terms of the approval itself — what is authorised, that the conditions are recorded against the parcel, printed on the plans, severable, and how they may be changed — and then the numbered or named conditions, grouped under section heads. The plans, Exhibit B, are cited and kept on file; they are not bound into the motion. That matters for what follows: the building’s shape is fixed by the plans, so a condition that changes it has to be written out, and most do not.

Table 10: The anatomy of one conditional-use motion, Motion No. 19244 (case 2014.0270C, adopted 2014-09-18), page by page. The document is chosen by rule: among the born-digital adopted conditional-use motions on the motion archive written in the modern template, the one whose condition count is closest to their median, ties broken by document identifier.

Part	Pages	What it is
Title block and summary of the request	1	Motion number, hearing date, case number, address, zoning, sponsor, staff contact; then the one-sentence statement of what the motion adopts.
Preamble	1–2	The application, its filing, the environmental determination and the hearing, recited as “whereas” facts.
Findings	2–11	The site, the surroundings, the project, public comment, and Planning Code compliance item by item.
the conditional-use finding (§303)	4	Whether the use is necessary or desirable and compatible with the neighbourhood, and not detrimental — the discretion itself.
the priority policies (§101.1)	10	The priority-policy findings, one paragraph each.
Decision	12	The approval, made subject to the conditions attached as Exhibit A and to the plans on file; the appeal period; and the adoption block with the roll call (p. 12).
Exhibit A: standing blocks	13	Authorization, Recordation of conditions of approval, Printing of conditions of approval on plans, Severability, Changes and modifications.
Exhibit A: Performance	14	5 conditions: Validity; Expiration and Renewal; Diligent pursuit; Extension; Conformity with Current Law.
Exhibit A: Monitoring	14–15	2 conditions: Enforcement; Revocation due to Violation of Conditions.
Exhibit A: Operation	15–16	6 conditions: Garbage, Recycling, and Composting Receptacles; Sidewalk Maintenance; Noise Control; Odor Control; Community Liaison; Closing Hours.
Exhibit B	—	The plans, cited by date in the decision (p. 12); kept on file and not bound into the motion.

3 Every standing section, and the most frequent headings

Table 11 lists the standing blocks and the section heads under which conditions are grouped, each with the number of motion sections carrying it, the share of conditional-use motions that carry it, the median length of a condition’s body under it, and the first and last hearing year it was seen. The 5 preamble blocks and the *Performance* and *Monitoring* sections are on the large majority of conditional-use motions, *Operation* and *Design* on most, and *Parking and Traffic* and *Provisions* on a minority — selected by project. The 1998–2009 motions group their conditions differently — “General Conditions”, or lettered parts such as “The Approved Project” and “Operation” with parenthesised conditions under each — and those appear as their own rows.

Table 11: The standing blocks of Exhibit A. Preamble blocks open it; the sections group the numbered conditions. ‘Motions’ counts motion sections carrying the block; ‘CU share’ is the share of conditional-use motions with conditions that carry it; ‘Chars’ the median length of a condition’s body under it.

Block	Motions	CU share	Chars	Conditions	Years
<i>Preamble blocks</i>					
AUTHORIZATION	3,675	88%	765	3,675	2007–2026
CHANGES AND MODIFICATIONS	3,685	88%	226	3,685	2007–2026
PRINTING ON PLANS	3,166	78%	370	3,166	2007–2026
RECORDATION	3,686	88%	462	3,686	2007–2026
SEVERABILITY	3,675	88%	444	3,675	2007–2026
<i>Condition sections</i>					
PERFORMANCE	3,679	89%	308	17,784	1989–2026
MONITORING	3,455	85%	462	9,831	1989–2026
OPERATION	3,194	78%	317	11,053	2007–2026
DESIGN	2,746	66%	418	9,866	2001–2026
PARKING AND TRAFFIC	1,464	31%	338	4,621	2003–2026
PROVISIONS	1,325	27%	204	4,959	2011–2026
AFFORDABLE HOUSING	233	3%	370	1,392	2003–2024
CONDITIONS OF APPROVAL	214	6%	274	2,610	1987–2025
(untitled list)					
ENTERTAINMENT	144	2%	511	306	2016–2026
COMMISSION NOISE					
ATTENUATION CONDITIONS					
GENERAL CONDITIONS	100	2%	438	695	2005–2024
MITIGATION MEASURES	38	1%	336	68	2001–2024
CONSTRUCTION	19	0%	316	115	1989–2024
BELOW MARKET RATE	14	0%	227	71	2009–2010
UNITS BMR UNITS					
TO BE COMPLETED BY	14	0%	105	88	2014–2023
PROJECT PLANNER					
EASTERN NEIGHBORHOODS	13	0%	645	13	2011–2014
INFRASTRUCTURE IMPACT					
FEE					
AUTHORIZATION	12	0%	673	21	2010–2014
OTHER	12	0%	138	12	2020–2025
HOUSING	11	0%	332	17	2009–2010

Block	Motions	CU share	Chars	Conditions	Years
SEISMIC HAZARD LANDSLIDE OR LIQUEFACTION HAZARD ZONE	11	0%	508	11	2020–2023
STEP 2 ENVIRONMENTAL SCREENING ASSESSMENT	11	0%	2,788	11	2020–2023
STEP 3 PROPERTY STATUS HISTORIC RESOURCE	11	0%	265	11	2020–2023
CHANGES AND MODIFICATIONS	10	0%	305	28	2011–2014
SIGNAGE	10	0%	167	11	2005–2016
TO BE COMPLETED BY PRESERVATION PLANNER	10	0%	106	100	2020–2023
PUBLIC ARTWORK	9	0%	362	33	2008–2016
STUDENT ENROLLMENT	9	0%	118	9	2014–2022
COMPLIANCE WITH OTHER REQUIREMENTS	8	0%	458	14	2001–2010
OPEN SPACE	8	0%	325	35	1989–2024
SEVERABILITY	8	0%	444	8	2011–2014
TRANSPORTATION	8	0%	438	42	1989–2024
APPROVED USE	7	0%	316	42	2009–2010
CONDITIONS					
LIGHTING	7	0%	362	7	2005–2008
STANDARD CONDITIONS	7	0%	521	77	2009–2010
THE APPROVED PROJECT	7	0%	309	24	2005–2008
CANNABIS RETAIL	6	0%	192	18	2021–2022
CONDITIONS TO BE MET PRIOR TO ISSUANCE OF ANY CERTIFICATES OF OCCUPANCY FOR THE PROJECT	6	0%	140	11	2009–2010
CONDITIONS TO BE MET PRIOR TO THE ISSUANCE OF A BUILDING OR SITE PERMIT	6	0%	154	15	2008–2010
MAXIMUM OCCUPANCY AND EVENTS	6	0%	389	22	2010–2023
PEDESTRIAN STREETSCAPE IMPROVEMENTS	6	0%	192	14	2001–2022
RECORDATION	6	0%	618	8	1989–2025
FIRST SOURCE HIRING	5	0%	537	5	2008–2011
PERMIT	5	0%	194	14	2008–2010
TRANSPORTATION DEMAND MANAGEMENT	5	0%	1,076	5	2017–2017

Table 12 gives the 40 most frequent condition headings, with the same statistics and three more: the share of the heading’s bodies that are *identical* to its most common body once numbers are masked — the part of the condition that never varies —, the share stating a quantity with a unit, and the commonest quantities stated. Sorted by those statistics, the headings fall into three kinds (a heading can fall in none).

- **A fixed text, with at most a number changing** (template share at least 80%; 21 head-

ings): Enforcement; Revocation due to Violation of Conditions; Conformity with Current Law; Validity; Expiration and Renewal; Diligent Pursuit; Sidewalk Maintenance; Final Materials; Rooftop Mechanical Equipment; Managing Traffic During Construction; Lighting; Garbage, Recycling, and Composting Receptacles; First Source Hiring; Transportation Sustainability Fee; Residential Child Care Impact Fee; Noise Control; Transportation Demand Management (TDM) Program; Overhead Wiring; Anti-Discriminatory Housing; Compatibility with City Emergency Services – WTS; Installation - WTS. Once the number is masked, most bodies are word for word the template; what a project changes, where it changes anything, is the figure.

- **A varying text that states a quantity** (template share below 80%, a quantity in at least 75% of bodies; 4): Bicycle Parking; Validity and Expiration; Hours of Operation; Transformer Vault. The figure is the point, and the sentence around it is rewritten to fit.
- **A recurring heading over a project-written body** (template share below 50%; 6): Community Liaison; Signage; Parking Maximum; Additional Project Authorization; Mitigation Measures; Car Share. The name recurs; what it asks for is written for the site.

What varies across projects, then, is hours, days, distances, counts of spaces and units, the period of validity, and the text of a few site-specific conditions; what does not vary is the enforcement and revocation apparatus and the clock. Table 13 quotes up to three bodies for each block and heading — the earliest, a typical one and the one least like the rest — each cut at 80 words, with the page of the source document and a link to it. Identical bodies are not repeated, so a block with one example has only one form.

Table 12: The 40 most frequent condition headings, by the number of motions carrying them. ‘CU’ is the share of conditional-use motions carrying it; ‘chars’ the median body length; ‘template’ the share of its bodies identical to its most common body once numbers are masked — the part that never varies; ‘quantity’ the share stating a number with a unit; ‘what varies’ the commonest stated quantities.

Heading	Motions	CU	Chars	Template	Quantity	Years	What varies
Enforcement	3,453	85%	462	94%	0%	2007–2026	—
Extension	3,435	83%	308	77%	0%	2007–2026	12 months; 33 feet; 27 feet
Revocation due to Violation of Conditions	3,317	82%	494	95%	0%	2007–2026	—
Community Liaison	3,141	77%	761	49%	2%	2005–2026	10 days; 300 feet; 25 percent
Conformity with Current Law	2,774	65%	191	97%	0%	2007–2026	—
Validity	2,769	65%	305	89%	97%	2007–2026	3 years; 5 years; 2 years
Expiration and Renewal	2,694	63%	657	96%	99%	2007–2026	3 years; 5 years; 2 years
Diligent Pursuit	2,690	63%	355	94%	99%	2007–2026	3 years; 2 years; 5 years
Sidewalk Maintenance	2,585	62%	244	93%	0%	2007–2026	8:00 a.m.
Garbage, Composting and Recycling Storage	1,905	44%	443	76%	0%	2007–2026	—
Final Materials	1,662	36%	321	84%	0%	2010–2026	45 percent; 15 feet; 5 feet

Heading	Motions	CU	Chars	Template	Quantity	Years	What varies
Bicycle Parking	1,223	26%	171	22%	99%	2008–2026	2 spaces; 11 spaces; 1 space
Rooftop Mechanical Equipment	999	20%	356	85%	0%	2011–2026	20 feet
Managing Traffic During Construction	963	18%	421	82%	0%	2011–2026	7:30 a.m.; 5 p.m.
Lighting	895	19%	344	91%	0%	2008–2026	—
Garbage, Recycling, and Composting Receptacles	892	21%	317	92%	0%	2007–2021	90 days; 7:00 a.m.; 10:00 p.m.
Validity and Expiration	821	23%	1,039	78%	98%	2007–2018	3 years; 18 months; 5 years
First Source Hiring	627	9%	371	86%	0%	2008–2026	—
Signage	625	16%	264	22%	1%	2008–2026	33 percent; 12 feet
Parking Maximum	596	12%	121	22%	7%	2011–2026	3.5 percent; 7 percent; 1.5 spaces
Monitoring	563	14%	292	64%	0%	2009–2026	—
Additional Project	551	9%	506	11%	13%	2012–2026	20 feet; 85 feet; 25 feet
Authorization							
Mitigation Measures	530	7%	249	38%	0%	2001–2026	—
Transportation	520	9%	125	89%	0%	2016–2026	50 percent
Sustainability Fee							
Residential Child Care	473	11%	112	96%	0%	2016–2026	13.5 percent; 20 percent; 35 percent
Impact Fee							
Streetscape Plan	462	8%	641	80%	1%	2011–2026	13 feet; 6 feet; 25 feet
Noise Control	396	10%	309	88%	0%	2010–2025	—
Hours of Operation	394	11%	125	4%	93%	2008–2026	6:00 a.m.; 10:00 p.m.; 2:00 a.m.
Transportation Demand Management (TDM) Program	369	5%	1,076	84%	0%	2017–2026	—
Noise	359	7%	169	80%	0%	2010–2026	12 a.m.
Odor Control Unit	349	8%	380	55%	0%	2010–2026	—
Transformer Vault	336	5%	1,360	24%	94%	2011–2020	12 feet
Overhead Wiring	328	5%	175	94%	0%	2011–2026	—
Eastern Neighborhoods	325	4%	132	53%	0%	2011–2025	—
Infrastructure Impact Fee							
Anti-Discriminatory	322	5%	134	96%	0%	2016–2026	—
Housing							
Car Share	298	4%	229	49%	4%	2011–2026	50 spaces; 3 spaces; 1 space
Lighting Plan	290	5%	166	77%	0%	2011–2026	—
Eating and Drinking Uses	287	7%	1,677	67%	0%	2017–2026	—
Compatibility with City	285	8%	313	96%	0%	2011–2026	6:02 p.m.; 10:50 a.m.; 3:08 p.m.
Emergency Services – WTS							
Installation - WTS	284	8%	321	99%	100%	2011–2026	10 days

Table 13: Verbatim examples, three to a block or heading where they differ: the earliest body, a typical one (the most common masked form, at median length), and the one least like the rest. Bodies are cut at 80 words; the reference gives the page of the source document and links to it.

Block or heading	Example
AUTHORIZATION	<i>early, 2007, p. 13, source</i>: This authorization is for a conditional use to allow a [Insert Use] (d.b.a. XXXXXX) located at [Insert Address, Block, and Lot] pursuant to Planning Code Section(s) XXXXXX within the XXXXXX District and a XXXXXX Height and Bulk District; in general conformance with plans, dated XXXXXX, and stamped “EXHIBIT B” included in the docket for Case No. XXXXXX and subject to conditions of approval reviewed and approved by the Commission on XXXXXX under Motion No XXXXXX. This authorization and the conditions . . . <i>typical, 2021, p. 23, source</i>: This authorization is for a Large Project Authorization for new construction of a nine-story, 92’ tall, 154,396 square feet (sq ft) mixed use building containing 168 dwelling units, 1,336 sq ft of Retail Sales and Service Use, and 47 off-street auto parking spaces, on a site currently developed as a private parking lot, located at 321 Florida Street on Block 3965, Lot 022, pursuant to Planning Code Sections 329 and 843, within the UMU Zoning District and 68-X Height and . . . <i>most unusual, 2023, p. 6, source</i>: This authorization is to modify Conditions of Approval related to validity, expiration, and renewal for the Project approved by the Commission on June 13, 2019, under Motion No. 20464. This motion authorized a Conditional Use Authorization for a planned unit development (PUD) to allow for 1) a development lot size exceeding 9,999 square feet (section 121.1), 2) conversion of an existing automotive service station (section 202.5), 3) bulk exception (section 271), and 4) demolition and replacement of three residential units . . .
CHANGES AND MODIFICATIONS	<i>early, 2007, p. 13, source</i>: Changes to the approved plans may be approved administratively by the Zoning Administrator. Significant changes and modifications of conditions shall require Planning Commission approval of a new Conditional Use authorization. <i>most unusual, 2021, p. 16, source</i>: Changes to the approved plans may be approved administratively by the Zoning Administrator. Significant changes and modifications of conditions shall require Planning Commission approval of a new Large Project authorization. 5. Conformity with Current Law. No application for Building Permit, Site Permit, or other entitlement shall be approved unless it complies with all applicable provisions of City Codes in effect at the time of such approval. 7. Extension. This authorization may be extended at the discretion of the Zoning Administrator . . .
PRINTING ON PLANS	<i>early, 2007, p. 13, source</i>: The conditions of approval under the ‘Exhibit A’ of this Planning Commission Motion No. XXXXXX shall be reproduced on the Index Sheet of construction plans submitted with the Site or Building permit application for the Project. The Index Sheet of the construction plans shall reference to the Conditional Use authorization and any subsequent amendments or modifications.

Block or heading	Example
RECORDATION	<i>most unusual, 2013, p. 38, source:</i> The conditions of approval under the “EXHIBIT A” of this Planning Commission Motion No. 18889 shall be reproduced on the Index Sheet of construction plans submitted with the site or building permit application for the Project. The Index Sheet of the construction plans shall refer to the Conditional Use authorization and any subsequent amendments or modifications. 6 The number of spaces allocated to each parking garage may vary, provided that the overall number of spaces for the Cathedral Hill Campus ... <i>early, 2007, p. 13, source:</i> Prior to the issuance of the building permit or commencement of use for the Project the Zoning Administrator shall approve and order the recordation of a Notice in the Official Records of the Recorder of the City and County of San Francisco for the subject property. This Notice shall state that the project is subject to the conditions of approval contained herein and reviewed and approved by the Planning Commission on XXXXXX under Motion No XXXXXX. <i>typical, 2014, p. 15, source:</i> Prior to the issuance of the building permit or commencement of use for the Project the Zoning Administrator shall approve and order the recordation of a Notice in the Official Records of the Recorder of the City and County of San Francisco for the subject property. This Notice shall state that the Project is subject to the conditions of approval contained herein and reviewed and approved by the Planning Commission on February 20, 2014 under Motion No. 19091. <i>most unusual, 2021, p. 14, source:</i> The conditions of approval under the ‘EXHIBIT A’ of this Planning Commission Motion No. XXXXXX shall be reproduced on the Index Sheet of construction plans submitted with the Site or Building Permit Application for the Project. The Index Sheet of the construction plans shall reference to the Conditional Use authorization and any subsequent amendments or modifications.
SEVERABILITY	<i>early, 2007, p. 13, source:</i> The Project shall comply with all applicable City codes and requirements. If any clause, sentence, section or any part of these conditions of approval is for any reason held to be invalid, such invalidity shall not affect or impair other remaining clauses, sentences, or sections of these conditions. This decision conveys no right to construct, or to receive a building permit. “Project Sponsor” shall include any subsequent responsible party. <i>most unusual, 2015, p. 121, source:</i> The Project shall, except as provided in and subject to the applicable provisions of the Development Agreement between 5M Project, LLC and the City and County of San Francisco for the 5M Project (the “DA”), comply with all applicable City codes and requirements. If any clause, sentence, section or any part of these conditions of approval is for any reason held to be invalid, such invalidity shall not affect or impair other remaining clauses, sentences, or sections of these conditions. ...
PERFORMANCE	<i>early, 1989, p. 31, source:</i> The authori zation and ri ght vested by vi rtue of thi s action shall be deemed void and cancelled, if within one year of this motion a site permi t has not been secured by Project Sponsor and if within eighteen months of this motion, site work has not begun on the Project. <i>typical, 2019, p. 13, source:</i> No application for Building Permit, Site Permit, or other entitlement shall be approved unless it complies with all applicable provisions of City Codes in effect at the time of such approval.

Block or heading	Example
MONITORING	<i>most unusual, 2020, p. 43, source:</i> The Project Sponsor must obtain approval of an Ordinance amending the General Plan to amend the Market and Octavia Plan; an Ordinance amending the Planning Code to update the Market and Octavia Area Plan; and an Ordinance amending the Zoning Map to change the height and bulk classifications on the Project site. The Project Sponsor must also obtain Conditional Use Authorization, pursuant to Section 303; an Office Allocation, pursuant to Section 321; and adoption of shadow findings, pursuant to Section . . .
	<i>early, 1989, p. 24, source:</i> the Central Permit Bureau shall collect \$5.000 prior to the issuance of the Building Permit in order to compensate the Department for the cost of monitoring compliance with Sections 149, 163, 164, 165 and 321 of the Code.
	<i>typical, 2019, p. 14, source:</i> Violation of any of the Planning Department conditions of approval contained in this Motion or of any other provisions of Planning Code applicable to this Project shall be subject to the enforcement procedures and administrative penalties set forth under Planning Code Section 176 or Section 176.1. The Planning Department may also refer the violation complaints to other city departments and agencies for appropriate enforcement action under their jurisdiction.
	<i>most unusual, 2016, p. 40, source:</i> Per Planning Code Section 415, the Project is required to provide information to the Mayor's Office of Housing (MOH) as follows: The Mayor's Office of Housing (MOH) is authorized to monitor this program. MOH shall develop a monitoring form and annual monitoring fee to be paid by the owner of the real property or the Post-Secondary Educational Institution or Religious Institutions, as defined in Section 102 of this Code. The owner of the real property and each Post-Secondary Educational . . .
OPERATION	<i>early, 2007, p. 21, source:</i> Garbage, recycling, and compost containers shall be kept within the premises and hidden from public view, and placed outside only when being serviced by the disposal company. Trash shall be contained and disposed of pursuant to garbage and recycling receptacles guidelines set forth by the Department of Public Works.
	<i>typical, 2021, p. 34, source:</i> The Project Sponsor shall maintain the main entrance to the building and all sidewalks abutting the subject property in a clean and sanitary condition in compliance with the Department of Public Works Streets and Sidewalk Maintenance Standards.
	<i>most unusual, 2016, p. 68, source:</i> Pursuant to Planning Code Section 138, the following areas shall be maintained as publicly accessible open space: Indoor Park "Urban Room" at ground level and viewing platform; the Public Sitting Area in a Pedestrian Walkway, adjacent to the proposed Elim Alley vacation; and the Mission Street Snippet "Pocket Park". Per Section 138, public availability to the Public Sitting Area in a Pedestrian Walkway and a Snippet is required at all times. Pedestrian access shall be maintained 24 hours per day, . . .
	<i>early, 2001, p. 26, source:</i> Highly reflective spandrel glass, mirror glass, or deeply tinted glass shall not be permitted. In no case shall visible daylight transmittance be less than 75 percent. Only clear glass shall be used at pedestrian levels.
DESIGN	

Block or heading	Example
PARKING AND TRAFFIC	<i>typical, 2021, p. 25, source</i>: Space for the collection and storage of garbage, composting, and recycling shall be provided within enclosed areas on the property and clearly labeled and illustrated on the building permit plans. Space for the collection and storage of recyclable and compostable materials that meets the size, location, accessibility and other standards specified by the San Francisco Recycling Program shall be provided at the ground level of the buildings. <i>most unusual, 2018, p. 26, source</i>: The Project Sponsor shall provide atwo-level underground parking garage, not three levels as originally proposed. The Project Sponsor shall work with Planning Department on the final design for the garage. <i>early, 2003, p. 65, source</i>: The proposal includes 33 off-street parking spaces, including 1 handicapped space. 27 parking spaces are required by the Planning Code. Of the 6 parking spaces exceeding the minimum requirement, a minimum of 2 shall be made available for the <i>typical, 2021, p. 28, source</i>: The Project Sponsor and construction contractor(s) shall coordinate with the Traffic Engineering and Transit Divisions of the San Francisco Municipal Transportation Agency (SFMTA), the Police Department, the Fire Department, the Planning Department, and other construction contractor(s) for any concurrent nearby Projects to manage traffic congestion and pedestrian circulation effects during construction of the Project. <i>most unusual, 2010, p. 36, source</i>: If the Project includes a retail use larger than 20,000 square feet, including but not limited to grocery, hardware, furniture, consumer electronics, greenhouse or nursery, and appliance stores, which sell merchandise that is bulky or difficult to carry by hand or by public transit, then the Project shall offer, at minimal or no charge to its customers, door-to-door delivery service and/or shuttle service, to meet the requirements of Section 151.1(f) of the Code.
PROVISIONS	<i>early, 2011, p. 27, source</i>: The Project shall adhere to the requirements of the First Source Hiring Construction and Employment Program approved by the First Source Hiring Administrator, pursuant to Section 83.4(m) of the Administrative Code. The Project Sponsor shall comply with the requirements of this Program regarding construction work and on-going employment required for the Project. <i>typical, 2021, p. 28, source</i>: The Project is subject to the Residential Child Care Fee, as applicable, pursuant to Planning Code Section 414A. <i>most unusual, 2013, p. 34, source</i>: Pursuant to Section 424.8, the Project Sponsor is required to participate in a Transit Center District Mello Roos Community Facilities District (CFD) and to include the area of the increment of additional gross floor area beyond the gross floor area approved for the Previous Project in the CFD prior to issuance of the First Temporary Certificate of Occupancy for the Project. The Project Sponsor must demonstrate compliance with this requirement prior to approval of the site permit by the Planning ...

Block or heading	Example
AFFORDABLE HOUSING	<i>early, 2003, p. 63, source:</i> Under Section 315 of the Planning Code, the project is subject to the Inclusionary Housing requirement. The number of below-market-rate (BMR) units required depends upon whether the affordable units are being provided on-site, off-site, or through payment of in lieu fees or the project applicant may choose a combination of two or three of the options. The project applicant shall make a final determination prior to issuance of the site/building permit for the approved project. A. If this requirement is . . . <i>typical, 2021, p. 30, source:</i> Under Planning Code Section 415.8, all units constructed pursuant to Section 415.6, must remain affordable to qualifying households for the life of the project. <i>most unusual, 2011, p. 26, source:</i> If the Project becomes ineligible at any time for the On-site Affordable Housing Alternative, the Project Sponsor or its successor shall pay the Affordable Housing Fee prior to issuance of the first construction permit or may seek a fee deferral as permitted under Ordinances 0107-10 and 0108-10. If the Project becomes ineligible after issuance of its first construction permit, the Project Sponsor shall notify the Department and MOH and pay interest on the Affordable Housing Fee at a rate equal . . .
CONDITIONS OF APPROVAL (untitled list)	<i>early, 1987, p. 63, source:</i> The authorization contained herein is for the use of the Subject Property as The Hamlin School and for addition to and expansion of said School generally as described in Application No. 87.439C and in plans marked Exhibit B on file with said Application with the exceptions that: (A) the second floor addition above the Hooker Laboratory building (and its height projected to the east) shall not exceed (and possibly be lower than) 13 feet; (B) said second floor addition to . . . <i>typical, 2008, p. 10, source:</i> Should monitoring of the Conditions of Approval contained in Exhibit A of this Motion be required, the Project Sponsor or successors shall pay fees as established in Planning Code Section 351(e)(1). <i>most unusual, 2010, p. 20, source:</i> A Building Permit from the Department of Building Inspection must be obtained to implement the approved use within three years from the effective date of Motion No. XXXX approving the proposed full-service restaurant. The Building Permit Application shall include plans in conformance with the plans on file with the Department in the docket for 2009.0996C (labeled EXHIBIT B), reviewed and approved by the Planning Commission on date February 25, 2010 under the Motion No. XXXX. The plans are required to . . .
ENTERTAINMENT COMMISSION NOISE ATTENUATION CONDITIONS	<i>early, 2016, p. 42, source:</i> The Project Sponsor shall comply with the “Recommended Noise Attenuation Conditions for Chapter 116 Residential Projects,” which were recommended by the Entertainment Commission on December 1, 2015. These conditions state: <i>typical, 2018, p. 16, source:</i> Project Sponsor shall include in its community outreach process any businesses located within 300 feet of the proposed project that operate between the hours of 9PM- 5AM. Notice shall be made in person, written or electronic form.

Block or heading	Example
GENERAL CONDITIONS	<i>most unusual, 2020, p. 26, source</i>: In addition to the “Recommended Noise Attenuation Conditions for Chapter 116 Residential Projects” detailed above, based on the proximity of the proposed Residential development to multiple Places of Entertainment, including the Oasis nightclub located within the same Block at 298 11th Street, the Project shall incorporate all recommended Noise Mitigation Measures as included in the June 26, 2020 Noise Study prepared by Wilson Ihrig, including the following: A. However, Project Sponsor shall incorporate windows with a minimum rating of STC ...
	<i>early, 2005, p. 18, source</i>: Final approval of a site or building permit for this project by the City shall be contingent on the final approval and adoption of the amendments to the Planning Code, the Zoning Maps Amendments, and other required actions required to finalize the new Rincon Hill Downtown Residential Mixed-use District.
	<i>typical, 2010, p. 21, source</i>: Prior to the issuance of any building permit for the construction of the Project, the Zoning Administrator shall approve and order the recordation of a notice in the Official Records of the Recorder of the City and County of San Francisco, which notice shall state that construction of the Project has been authorized by and is subject to the conditions of this Motion. From time to time after the recordation of such notice, at the request of the Project Sponsor, ...
MITIGATION MEASURES	<i>most unusual, 2010, p. 14, source</i>: The plywood sheathing proposed to be mounted to the rooftop guardrail on the south and west elevations shall also be mounted on the east elevation. This sheathing shall be painted and textured to match the existing building.
	<i>early, 2001, p. 7, source</i>: Building 1 shall be subject to, and the Project Sponsor shall implement the mitigation measures set forth in and otherwise comply with, the Mitigation Monitoring and Reporting Program (“MMRP”) as detailed in Exhibit C of Motion 15006 and incorporated herein by this reference.
	<i>typical, 2010, p. 39, source</i>: Mitigation measures described in the MMRP attached as Exhibit C are necessary to avoid potential significant effects of the proposed project and have been agreed to by the project sponsor. Their implementation is a condition of project approval.
CONSTRUCTION	<i>most unusual, 2024, p. 63, source</i>: Project Sponsor shall develop a site mitigation plan for the project activities. The site mitigation plan will be based upon a risk assessment quantifying potential risk of exposure to site workers and future site occupants due to excavated and remaining contaminated soils. The plan will be signed by a qualified person pursuant to Article 20 who will certify (as defined in Article 20) that the plan, if carried out, will mitigate any significant environmental, health or safety risks that could ...
	<i>early, 1989, p. 21, source</i>: If pile driving is required, the Project Sponsor shall pre-auger holes for piles unless the Project Sponsor can establish, to the , that sati sfaction of the Bureau of Bui 1 di ng Inspection (BB!) such a procedure is unnecessary or undesirable.
	<i>typical, 2008, p. 19, source</i>: The Project Sponsor shall ensure the construction contractor will coordinate with the City and other construction contractor(s) for any concurrent nearby projects that are planned for construction so as to minimize, to the extent possible, negative impacts on traffic and nearby properties caused by construction activities.

Block or heading	Example
BELOW MARKET RATE UNITS BMR UNITS	<i>most unusual, 2024, p. 66, source</i>: Should dewatering be necessary, the final soils and foundation report shall address the potential settlement and subsidence impacts of dewatering of the site. Based upon this discussion the report shall contain a determination as to whether or not a lateral movement and settlement survey should be done to monitor any horizontal or vertical movement of surrounding buildings and adjacent streets. If a monitoring survey is recommended, the Department of Public Works will require that a Special Inspector (as defined in . . . <i>early, 2009, p. 24, source</i>: Pursuant to Planning Code 415.7 (formerly Code Section 315.4), the Project Sponsor must pay an Affordable Housing fee at a rate equivalent to the applicable percentage of the number of units in the principle project to satisfy the Affordable Housing Requirement. The applicable percentage for this project is twenty percent (20%). <i>typical, 2010, p. 29, source</i>: The BMR units shall be designated on a reduced set of plans recorded as a Notice of Special Restrictions on the Property prior to the issuance of the first site or building permit. <i>most unusual, 2010, p. 29, source</i>: Pursuant to Planning Code Section 315.6, the Project is required to provide 15% of the proposed dwelling units as affordable to qualifying households (“BMR Units”).
TO BE COMPLETED BY PROJECT PLANNER	<i>early, 2014, p. 18, source</i>: If neither class applies, an Environmental Evaluation Application is required. Class 1 - Existing Facilities. Interior and exterior alterations; additions under 10,000 sq. ft.; change principally permitted Ei of use under 10,000 sq. ft. if or with a CU. Class 3 New Construction. Up to three (3) new single-family residences or six (6) dwelling units in one building; commercial/office structures; utility extensions. <i>typical, 2020, p. 20, source</i>: Tenant improvements not included. <i>most unusual, 2020, p. 18, source</i>: Would the project add new sensitive receptors (specifically, schools, day care facilities, hospitals, residential dwellings, and senior-care facilities within an Air Pollution Exposure Zone? Does the project have the potential to emit substantial pollutant concentrations (e.g., backup diesel generators, heavy industry, diesel trucks, etc.)? (refer to EP ArcMap > CEQA Catex Determination Layers > Air Pollution Exposure Zone) Hazardous Materials: If the project site is located on the Maher map or is suspected of containing hazardous materials (based on . . .
EASTERN NEIGHBORHOODS INFRASTRUCTURE IMPACT FEE	<i>early, 2011, p. 20, source</i>: The project shall comply with the provisions of Planning Code Section 423, including payment of the Eastern Neighborhoods Impact Fee, or execution of an In-Kind Agreement with the Planning Department prior to issuance of the first site or building permit. While recognizing that the Commission will review any use of the Eastern Neighborhoods Impact Fee in the future, the Commission urges the Project Sponsor to pursue the execution of an In-Kind Agreement pursuant to Planning Code Section 423.3(d) to authorize . . . <i>most unusual, 2014, p. 28, source</i>: Pursuant to Planning Code Section 423 (formerly 327), the Project Sponsor shall comply with the Eastern Neighborhoods Public Benefit Fund provisions through payment of an Impact Fee pursuant to Article 4.

Block or heading	Example
AUTHORIZATION	<i>early, 2010, p. 25, source:</i> This authorization is for a Conditional Use to establish a new formula retail grocery store (dba Whole Foods Market) with the ability to operate 24 hours per day, on the adjacent lots of 690 Stanyan Street (Assessor’s Block 1228, Lots 005 & 006), pursuant to Planning Code Sections 303, 703.4, and 719.27, within the Haight Street Neighborhood Commercial District, Haight Alcohol Restricted Subdistrict and 40-X and 50-X Height and Bulk District, in general conformance with plans filed with the Application . . . <i>typical, 2014, p. 39, source:</i> The “Mitigation Monitoring and Reporting Program,” attached herein as EXHIBIT C and which identifies Mitigation Measures and Improvement Measures to be included as part of the project as outlined in the Final Case No. 2011.1306C, shall be Conditions of Approval and are accepted by the project applicant and the successors-in-interest. If any measures of the Mitigation Monitoring and Reporting Program are less restrictive than the following conditions of approval, the more restrictive and more protective condition of approval shall apply. <i>most unusual, 2011, p. 74, source:</i> This authorization is for a conditional use to allow new construction of a Planning Unit Development consisting of a five-story-over-basement, 55-foot-tall mixed-use building (containing community facility uses, up to 50 units of affordable housing and 21 off-street parking spaces, of which 24 units are affordable to low income households and 24 units are for low and very low income transitional aged youth)located at 800 Presidio Avenue, Block 013 in Assessor’s Lot 1073 pursuant to Planning Code Sections 303 and 304 within . . .
OTHER	<i>early, 2020, p. 18, source:</i> It can be seen with certainty that there is no possibility of a significant effect on the environment. FOR ENVIRONMENTAL PLANNING USE ONLY <i>most unusual, 2021, p. 20, source:</i> It can be seen with certainty that there is no possibility of a significant effect on the environment.
HOUSING	<i>early, 2009, p. 33, source:</i> The Project’s dwelling units shall not be marketed for time-share or short-term transient use. No residential units shall be used as hotel units. <i>typical, 2010, p. 36, source:</i> Covenants, conditions and restrictions approved by the Planning Department shall be imposed upon the project units to restrict use to occupancy for permanent residents and to preclude time-share ownership or occupancy. No residential units shall be used as hotel units, as defined in Section 203.8 of the San Francisco Housing Code. <i>most unusual, 2010, p. 29, source:</i> The Project Sponsor community liaison shall work with the Mission Hiring Hall South of Market Employment Center to evaluate qualified and competitively priced firms and service providers that have historically done work in or provided services in the SoMa Redevelopment Plan Area and make good faith efforts to engage such firms and service providers based on their qualifications and competitive costs and rates on an as needed basis.
SEISMIC HAZARD LANDSLIDE OR LIQUEFACTION HAZARD ZONE	<i>early, 2020, p. 19, source:</i> (1) New building construction, except one-story storage or utility occupancy, (2) horizontal additions, if the footprint area increases more than 50%, (3) horizontal and vertical additions increase more than 500 square feet of new projected roof area, or (4) grading performed at a site in the landslide hazard zone? (refer to The Environmental tab on the San Francisco Property Information Map) If box is checked, a geotechnical report is required and Environmental Planning must issue the exemption.

Block or heading	Example
STEP 2 ENVIRONMENTAL SCREENING ASSESSMENT	<i>most unusual, 2021, p. 21, source:</i> (1) New building construction, except one-story storage or utility occupancy, (2) horizontal additions, if the footprint area increases more than 50%, (3) horizontal and vertical additions increase more than 500 square feet of new projected roof area, or (4) grading performed at a site in the landslide hazard zone? (refer to the Environmental Information tab on https://sfplanninggis.org/PIM/) If box is checked, a geotechnical report is required and Environmental Planning must issue the exemption. Don Lewis <i>early, 2020, p. 19, source:</i> Would the project add new sensitive receptors (specifically, schools, day care facilities, hospitals, residential dwellings, and senior-care facilities within an Air Pollution Exposure Zone? Does the project have the potential to emit substantial pollutant concentrations (e.g. use of diesel construction equipment, backup diesel generators, heavy industry, diesel trucks, etc.)? (refer to The Environmental Information tab on the San Francisco Property Information Map) Hazardous Materials: If the project site is located on the Maher map or is suspected of containing hazardous ...
STEP 3 PROPERTY STATUS HISTORIC RESOURCE	<i>most unusual, 2021, p. 21, source:</i> Would the project add new sensitive receptors (specifically, schools, day care facilities, hospitals, residential dwellings, and senior-care facilities within an Air Pollution Exposure Zone? Does the project have the potential to emit substantial pollutant concentrations (e.g. use of diesel construction equipment, backup diesel generators, heavy industry, diesel trucks, etc.)? (refer to the Environmental <i>early, 2020, p. 20, source:</i> (refer to Property Information Map) Category A: Known Historical Resource. GO TO STEP 5. Category B: Potential Historical Resource (over 45 years of age). GO TO STEP 4. Category C: Not a Historical Resource or Not Age Eligible (under 45 years of age). GO TO STEP 6.
CHANGES AND MODIFICATIONS	<i>early, 2011, p. 16, source:</i> Changes to the approved plans may be approved administratively by the Zoning Administrator. Significant changes and modifications of conditions shall require Planning Commission approval of a new Conditional Use authorization. <i>most unusual, 2011, p. 31, source:</i> The authorization and right vested by virtue of this action is valid for three years from the effective date of the Motion. A building permit from the Department of Building Inspection to construct the project and/or commence the approved use must be issued as this Conditional Use authorization is only an approval of the proposed project and conveys no independent right to construct the project or to commence the approved use. The Planning Commission may, in a public hearing, consider ...
SIGNAGE	<i>early, 2005, p. 53, source:</i> All Project signage shall be consistent with the controls of Article 6 of the Planning Code and shall be reviewed and approved by the Planning Department. <i>typical, 2008, p. 10, source:</i> All Project signage shall be consistent with the controls of Article 6 of the Planning Code. Project signage shall be reviewed and approved by the Planning Department. <i>most unusual, 2006, p. 89, source:</i> A landscape plan shall be prepared by a licensed architect or landscape architect and submitted to the Planning Department for review and approval prior to the approval of any building permit applications.

Block or heading	Example
TO BE COMPLETED BY PRESERVATION PLANNER	<i>early, 2020, p. 20, source:</i> (Attach HRER Part I) Reclassify to Category A Reclassify to Category C a. Per HRER (No further historic review) b. Other (specify): <i>typical, 2020, p. 20, source:</i> Project involves a known historical resource (CEQA Category A) as determined by Step 3 and conforms entirely to proposed work checklist in Step 4. <i>most unusual, 2020, p. 21, source:</i> in a manner that does not remove, alter, or obscure character-defining features.
PUBLIC ARTWORK	<i>early, 2008, p. 21, source:</i> The Project shall include the work(s) of art valued at an amount equal to one percent of the hard construction costs for the Project as determined by the Director of the Department of Building Inspection. The Project Sponsor shall provide to the Director necessary information to make the determination of construction cost hereunder. <i>most unusual, 2010, p. 27, source:</i> The building design shall provide adequate space designated for trash compactors and trash loading. Space for the collection and storage of recyclable materials that meets the size, location, accessibility and other standards specified by the San Francisco Recycling Program, shall also be provided. Enclosed trash areas with provisions for separating recyclable and non-recyclable materials shall be provided for Project residents on each floor of the residential tower. These areas shall be indicated on the building plans.
STUDENT ENROLLMENT	<i>early, 2014, p. 22, source:</i> Enrollment for the Presidio Hill School shall be limited to 240 students when the 233 Maple Street building is ready for student occupancy. <i>typical, 2020, p. 21, source:</i> Enrollment for the Project shall be up to a total of 250 students.
COMPLIANCE WITH OTHER REQUIREMENTS	<i>early, 2001, p. 28, source:</i> This decision conveys no right to construct, or to receive a building permit. The Project Sponsor must obtain a project approval under Section 309, and satisfy all the conditions thereof, including mitigation measures addressing environmental impacts. The conditions set forth below are additional conditions required in connection with the Project. If these conditions overlap with any other requirement imposed on the Project, the more restrictive or protective condition or requirement, as determined by the Zoning Administrator, shall apply. <i>typical, 2010, p. 21, source:</i> This decision conveys no right to construct. The conditions set forth below are additional conditions required in connection with the Project. If these conditions overlap with any other requirement imposed on the Project, the more restrictive or protective condition or requirement, as determined by the Zoning Administrator, shall apply. The conditions set forth below shall remain in effect for the life of the Project, unless specifically noted otherwise. <i>most unusual, 2010, p. 27, source:</i> The approved density of 28 affordable dwelling units is contingent on the Board of Supervisors enacting the ordinance to rezone the Subject Property from P (Public) to RH-1 (Residential House: One-Family). If the Map Amendment is not approved, the Project will not be permitted on the Property.
OPEN SPACE	<i>early, 1989, p. 24, source:</i> The Project Sponsor shall place an informational plaque for Project open space conforming to the requirements of Planning Code Section 138(i). B. Public Artwork; Recognition of Architect and Artists <i>typical, 2001, p. 27, source:</i> The Project shall include the open space described generally in this Motion.

Block or heading	Example
SEVERABILITY	<i>most unusual, 2001, p. 8, source</i>: Public Artwork; Recognition of Architect and Artists (1) The Project Sponsor shall install one or more works of art on each Area in the Project with a value equal to 1% of the hard construction costs of the building on each development site as determined by the Director of the Department of Building Inspection. The Certificate of Occupancy on each site is contingent on the installation of art on that Area only. If the Zoning Administrator concludes that it is ... <i>early, 2011, p. 15, source</i>: The Project shall comply with all applicable City codes and requirements. If any clause, sentence, section or any part of these conditions of approval is for any reason held to be invalid, such invalidity shall not affect or impair other remaining clauses, sentences, or sections of these conditions. This decision conveys no right to construct, or to receive a building permit. "Project Sponsor" shall include any subsequent responsible party.
TRANSPORTATION	<i>early, 1989, p. 25, source</i>: The Project Sponsor shall execute a Memorandum of Agreement for Transportation Management with the Department, for the provision of a Transportation Management program in compliance with the then currently adopted guidelines for Section 163. <i>typical, 2010, p. 18, source</i>: The Project Sponsor shall maintain an on-site parking area, which through the use of a parking attendant during funeral and memorial services can accommodate approximately 43 vehicles. <i>most unusual, 1989, p. 29, source</i>: Parking operations shall provide for a minimum of 15 short term spaces for exclusive use by business visitors and clients. All parking included in this minimum allocation is subject to the rate structure set forth in Section 155(g). Leasing, assignment, prepayment, designation for use by any individual or firm, or any other encumbrance of short-term parking spaces shall be prohibited. Parking operations shall also provide for a minimum of 10 spaces designated for Project employee preferential rideshare parking, and shall ...
APPROVED USE CONDITIONS	<i>early, 2009, p. 59, source</i>: This Conditional Use approval is to convert vacant commercial space with approximately 1,000 square feet of floor area for occupancy by a massage establishment (dba Perfect Health Center) on the ground floor of an existing three-story commercial and residential building, within the NC-3 (Moderate-Scale) Neighborhood Commercial District and a 40-X Height and Bulk District, in general conformity with Plans on file with the Department in the docket for Case No. 2009.0580C (labeled EXHIBIT B), reviewed and approved by the Commission ... <i>typical, 2010, p. 11, source</i>: The property owner shall maintain the main entrance to the building and all sidewalks abutting the Subject Property in a clean condition. Such maintenance shall include, at a minimum, daily litter pickup and disposal, and washing or steam cleaning or the main entrance and abutting sidewalks at least once each week. <i>most unusual, 2010, p. 14, source</i>: The proposal is to convert a vacant retail sales establishment (previously occupied by "Aveda") to another retail sales establishment (dba BoConcept, a contemporary design furniture and accessories store). The proposed retail store, with approximately 2,300 square feet in floor area, is considered a Formula Retail Use under Section 703.3 of the Planning Code. The proposal will involve interior and exterior tenant improvements to the existing commercial space. There will be no expansion of the existing building envelope.
LIGHTING	<i>early, 2005, p. 53, source</i>: All Project lighting shall be directed onto the Project Site and immediately surrounding sidewalk area only.

Block or heading	Example
STANDARD CONDITIONS	<i>typical, 2008, p. 11, source:</i> All Project lighting shall be directed onto the Project Site and immediately surrounding sidewalk area only, and designed and managed so as not to be a nuisance to surrounding residents and businesses. Nighttime lighting shall be the minimum necessary to ensure safety, but shall in no case be directed so as to constitute a nuisance to any surrounding property. <i>early, 2009, p. 60, source:</i> This Conditional Use approval is valid for three years from the effective date of Motion No. 17955 authorizing the proposed massage establishment use and shall automatically expire on September 24, 2012. This authorization is just an approval of the proposed use and is NOT a permit to implement the approved use. This authorization and right vested by virtue of this action shall be deemed void and cancelled if a Building Permit from the Department of Building Inspection to implement the ... <i>typical, 2010, p. 12, source:</i> Minor changes to the approved plans may be approved administratively by the Zoning Administrator. Major changes and modifications of conditions shall be subject to review and approval by the Planning Commission requiring a new Conditional Use approval or amendment to this Conditional Use approval as determined by the Zoning Administrator. Such changes must be requested prior to the expiration of this Conditional Use approval. <i>most unusual, 2010, p. 21, source:</i> COMPLETION OF BUILDING PERMIT The completion of Building Permit with a final inspection and/or issuance of a Certificate of Final Completion and Certificate of Occupancy from the Department of Building Inspection for the comply with all approved use under this project shall be deemed acceptance and agreement to fully of the conditions of approval of this Conditional Use approval. The project sponsor or the responsible party must ensure that the Building Permit Application has attained a 'complete' stage within the ...
THE APPROVED PROJECT	<i>early, 2005, p. 52, source:</i> This approval is to modify an existing Conditional Use authorization for a Planned Unit Development under Motion No. 13578 (for Case No. 1992.498C at 3065 Jackson Street) for the establishment of a new institutional/education facility (San Francisco University High School Annex Campus) at 3220 Sacramento Street; to allow an institutional/educational use on the second and third floors; to allow a non-residential use size that exceeds 2,500 square feet, and on a development lot that exceeds 5,000 square feet in area. ... <i>typical, 2008, p. 10, source:</i> Building area and massing authorized herein is limited to that described on the plans labeled EXHIBIT B. The Applicant shall advise the Planning Department staff of any changes or modifications to the Project, which would result in any deviation from the plans (labeled EXHIBIT B), as approved in this Motion. <i>most unusual, 2005, p. 52, source:</i> The Project Sponsor shall regulate the comportment of its student body, including Summerbridge, fifteen minutes before, after and during all scheduled hours of student presence by providing monitors to assure orderly drop-off and pick-up of students, and that students cross legally and without excessive noise between the Lower, Middle, Upper and Annex campuses, do not litter, and do not loiter or eat lunch on the public streets or neighboring private properties.
CANNABIS RETAIL	<i>early, 2021, p. 17, source:</i> On-site consumption of packaged or prepared cannabis products is permitted as an accessory use to this Cannabis Retail use. On-site smoking or vaporizing of cannabis products is not permitted.

Block or heading	Example
CONDITIONS TO BE MET PRIOR TO ISSUANCE OF ANY CERTIFICATES OF OCCUPANCY FOR THE PROJECT	<i>typical, 2022, p. 21, source</i>: The checking of identification cards to verify that patrons of the Cannabis Retail establishment meet minimum age requirements shall occur within the licensed premises if possible. <i>most unusual, 2022, p. 21, source</i>: The Project Sponsor shall obtain operating licenses from the City’s Office of Cannabis and the State of California prior to commencing any cannabis sales or other cannabis related activities per Planning Code Section 202.2(a)(5). <i>early, 2009, p. 21, source</i>: All usable open spaces shall be completed and available for use.
CONDITIONS TO BE MET PRIOR TO THE ISSUANCE OF A BUILDING OR SITE PERMIT	<i>typical, 2010, p. 38, source</i>: An evacuation and emergency response plan shall be developed by the Project Sponsor or building management staff, in consultation with the Mayors Office of Emergency Services, to ensure coordination between the Citys emergency planning activities and the Projects plan and to provide for building occupants in the event of an emergency. The Projects plan shall be reviewed by the Office of Emergency Services and implemented by the building management insofar as feasible before issuance of the final certificate of occupancy . . . <i>early, 2008, p. 20, source</i>: The Project Sponsor and the Project architects shall continue to work on aspects of design development with the Department.
MAXIMUM OCCUPANCY AND EVENTS	<i>most unusual, 2010, p. 25, source</i>: A final pedestrian streetscape improvement plan including landscaping and paving materials and patterns, shall be submitted for review by, and shall be satisfactory to the Director of the Department, in consultation with staff from the Department of Public Works and the Department of Parking and Traffic. Other agencies shall be contacted as appropriate. The Project shall include pedestrian streetscape improvements as described in this Motion and in conformance with Planning Code Section 138.1, Section 143, and the Downtown Streetscape Plan. <i>early, 2010, p. 20, source</i>: No more than 3,500 patrons shall be permitted for events in the auditorium on the main floor level and mezzanine of the Masonic Center. <i>most unusual, 2010, p. 20, source</i>: There shall be an annual maximum of 95 live entertainment events held at the Masonic Center that start at 7:00PM or later, of which no more than 70 live entertainment events may utilize general admission attendance without assigned seating for patrons in the lower (floor) level of the auditorium. There shall be an annual maximum of 20 events not involving live entertainment that are held at the Masonic Center and start at 7:00PM or later. There shall be no limitations . . .
PEDESTRIAN STREETSCAPE IMPROVEMENTS	<i>early, 2001, p. 26, source</i>: The Project shall include pedestrian streetscape improvements generally as described in this Motion and in conformance with Section 138.1. <i>typical, 2008, p. 21, source</i>: The Project Sponsor shall complete the Citys standard pedestrian streetscape improvements as required by the Department of Public Works and shall be responsible for the upkeep and maintenance of such improvements if they exceed City standards.

Block or heading	Example
RECORDATION	<i>most unusual, 2008, p. 21, source</i>: Street trees shall be installed pursuant to the requirements set forth in Section 143. The species and locations shall be subject to approval by the Department of Public Works. <i>early, 1989, p. 23, source</i>: Prior to the issuance of any building permit for the construction of the Project, the Zoning Administrator shall approve and order the recordation of a notice in the Official Records of the Recorder of the City and County of San Francisco, which notice shall state that construction of the Project has been authorized by and is subject to the conditions of this Motion. From time to time after the recordation of ... <i>typical, 2025, p. 46, source</i>: Prior to the issuance of any building permit for the construction of the Project, the Zoning Administrator shall approve and order the recordation of a notice in the Official Records of the Recorder of the City and County of San Francisco, which notice shall state that construction of the Project has been authorized by and is subject to the conditions of this Motion. From time to time after the recordation of such notice, at the request of ...
FIRST SOURCE HIRING	<i>most unusual, 2008, p. 12, source</i>: The Project Sponsor shall assure the execution and recordation of the specified conditions as a Notice of Special Restrictions at the Office of the County Recorder / County Clerk. <i>early, 2008, p. 14, source</i>: The Project is subject to the requirements of the First Source Hiring Program (Chapter 83 of the Administrative Code) and the Project Sponsor shall comply with the requirements of this program, including having an Occupancy Program approved by the First Source Hiring Administrator prior to the issuance of the first Certificate of Occupancy. <i>typical, 2011, p. 58, source</i>: The Project is subject to the requirements of the First Source Hiring Program as they apply to permits for residential development (Section 83.4(m) of the Administrative Code), and the Project Sponsor shall comply with the requirements of this Program as to all construction work and on-going employment required for the Project. Prior to the issuance of the Site Permit, the Project Sponsor shall have a First Source Hiring Construction and Employment Program approved by the First Source Hiring Administrator, ...
PERMIT	<i>most unusual, 2010, p. 43, source</i>: The Project shall adhere to the requirements of the First Source Hiring Construction and Employment Program approved by the First Source Hiring Administrator as they apply to permits for residential development (Section 83.4(m) of the Administrative Code). The Project Sponsor shall comply with the requirements of this Program regarding construction work and on-going employment required for the Project. <i>early, 2008, p. 15, source</i>: Except as otherwise provided in the attached Motion, the Project shall be completed in compliance with the Planning Code and in general conformity with plans labeled Exhibit B, dated May 29, 2008. <i>typical, 2010, p. 56, source</i>: The Project Sponsor and the Project architects shall continue to work on aspects of design development with the Department.

Block or heading	Example
TRANSPORTATION DEMAND MANAGEMENT	<i>most unusual, 2010, p. 21, source</i>: A final pedestrian streetscape improvement plan, including landscaping and paving materials and patterns, shall be submitted for review by, and shall be satisfactory to the Planning Director, in consultation with staff from the Department of Public Works, the Department of Parking and Traffic, and the Bureau of Urban Forestry. Other agencies shall be contacted as appropriate. The Project shall include street trees in conformance with Section 143. The street trees planted pursuant to this condition shall be maintained in perpetuity . . . <i>early, 2017, p. 53, source</i>: Pursuant to Planning Code Section 169, the Project shall finalize a TDM Plan prior to the issuance of the first Building Permit or Site Permit to construct the project and/or commence the approved uses. The Property Owner, and all successors, shall ensure ongoing compliance with the TDM Program for the life of the Project, which may include providing a TDM Coordinator, providing access to City staff for site inspections, submitting appropriate documentation, paying application fees associated with required monitoring and . . .
Enforcement	<i>early, 2007, p. 15, source</i>: Violation of any of the Planning Department conditions of approval contained in this Motion or of any other provisions of Planning Code applicable to this Project shall be subject to the enforcement procedures and administrative penalties set forth under Planning Code Section 176 or Section 176.1. The Planning Department may also refer the violation complaints to other city departments and agencies for appropriate enforcement action under their jurisdiction. <i>most unusual, 2011, p. 14, source</i>: The Project Sponsor shall demonstrate operation as a full-service restaurant and abate all active Code Enforcement violations, including Complaint No. 11284 and Complaint No. 6524, prior to building permit approval and use of the outdoor activity area.
Extension	<i>early, 2007, p. 14, source</i>: All time limits in the preceding three paragraphs may be extended at the discretion of the Zoning Administrator where implementation of the project is delayed by a public agency, an appeal or a legal challenge and only by the length of time for which such public agency, appeal or challenge has caused delay. <i>most unusual, 2013, p. 25, source</i>: This authorization may be extended at the discretion of the Zoning Administrator only where failure to issue a permit by the Department of Building Inspection to perform said tenant improvements is caused by a delay by a local, State or Federal agency or by any appeal of the issuance of such permit(s). Mitigation Measures. Mitigation measures described in the MMRP attached as Exhibit C are necessary to avoid potential significant effects of the proposed project and have been agreed to . . .
Revocation due to Violation of Conditions	<i>early, 2007, p. 15, source</i>: Should implementation of this Project result in complaints from interested property owners, residents, or commercial lessees which are not resolved by the Project Sponsor and found to be in violation of the Planning Code and/or the specific conditions of approval for the Project as set forth in Exhibit A of this Motion, the Zoning Administrator shall refer such complaints to the Commission, after which it may hold a public hearing on the matter to consider revocation of this authorization.

Block or heading	Example
Community Liaison	<i>most unusual, 2026, p. 19, source</i>: Should the project be found to be violation of the Planning Code and/or the specific conditions of approval for the Project as set forth in Exhibit A of this Motion that are not resolved and abated, the Zoning Administrator may refer such complaints to the Commission, after which it may hold a public hearing on the matter to consider revocation of this authorization. <i>early, 2005, p. 19, source</i>: The Project Sponsor shall appoint a community liaison officer to deal with issues of concern to the owners and occupants of nearby properties at all times during Project construction. Prior to the commencement of Project construction, the Project Sponsor shall give the Zoning Administrator and the owners of properties within 300 feet of the Project site boundaries written notice of the name, business address and telephone number of the community liaison. <i>typical, 2021, p. 34, source</i>: Prior to issuance of a building permit to construct the project and implement the approved use, the Project Sponsor shall appoint a community liaison officer to deal with the issues of concern to owners and occupants of nearby properties. The Project Sponsor shall provide the Zoning Administrator and all registered neighborhood groups for the area with written notice of the name, business address, and telephone number of the community liaison. Should the contact information change, the Zoning Administrator and registered . . . <i>most unusual, 2016, p. 25, source</i>: Prior to issuance of a building permit to construct the project and implement the approved use, the Project Sponsor shall appoint a community liaison officer to
Conformity with Current Law	<i>early, 2007, p. 14, source</i>: No application for Building Permit, Site Permit, or other entitlement shall be approved unless it complies with all applicable provisions of City Codes in effect at the time of such approval. <i>most unusual, 2015, p. 28, source</i>: No application for Building Permit, Site Permit, or other entitlement shall be approved unless it complies with all applicable provisions of City Codes in effect at the time of such approval. Additional Project Authorization. The Project Sponsor must obtain a variance from the Zoning Administrator to address the Planning Code requirements for open space (Planning Code Section 135) and exposure (Planning Code Section 140), and satisfy all the conditions thereof. The conditions set forth below are additional conditions required in . . .
Validity	<i>early, 2007, p. 14, source</i>: The authorization and right vested by virtue of this action is valid for three (3) years from the effective date of the Motion. The Department of Building Inspection shall have issued a Building Permit or Site Permit to construct the project and/or commence the approved use within this three-year period. <i>most unusual, 2013, p. 17, source</i>: Use is authorized as long as an independent evaluator determines that the information and conclusions submitted by AT&T Mobility in support of its request for conditional use are accurate. AT&T Mobility shall fully cooperate with the evaluator and shall provide any and all data requested by the evaluator to allow the evaluator to verify that the maps, data and conclusions about service coverage submitted by AT&T Mobility are accurate. AT&T Mobility shall bear all costs of said evaluation. The independent . . .

Block or heading	Example
Expiration and Renewal	<i>early, 2007, p. 14, source</i>: Should a Building or Site Permit be sought after the three (3) year period has lapsed, the project sponsor must seek a renewal of this Authorization by filing an application for an amendment to the original Authorization or a new application for Authorization. Should the project sponsor decline to so file, and decline to withdraw the permit application, the Commission shall conduct a public hearing in order to consider the revocation of the Authorization. Should the Commission not revoke the . . . <i>most unusual, 2023, p. 14, source</i>: This Coastal Zone Permit shall expire on December 31, 2025. Pursuant to Planning Code Section 330.13(a) a final decision on an application for an appealable Project shall become effective after a 10 working day appeal period to the California Coastal Commission has expired, unless either of the following occur: (1) a valid appeal is filed in accordance with City and State regulations, or (2) local government requirements are not met per Section 330.6(b). When either of the above occur, the . . .
Diligent Pursuit	<i>early, 2007, p. 14, source</i>: Once a site or Building Permit has been issued, construction must commence within the timeframe required by the Department of Building Inspection and be continued diligently to completion. Failure to do so shall be grounds for the Commission to consider revoking the approval if more than three (3) years have passed since this Authorization was approved. <i>most unusual, 2021, p. 21, source</i>: Once the first Site or Building Permit has been issued, construction must be continued diligently to achieve completion of all office space and required affordable housing obligations within the 30-year term of the Development Agreement, taking into consideration market conditions and the feasibility of constructing new buildings given the unimproved nature of the Project Site and the requirement that major new horizontal infrastructure (such as streets and utility systems) be completed prior to vertical development. Failure to do so shall . . .
Sidewalk Maintenance	<i>early, 2007, p. 21, source</i>: The Project Sponsor shall maintain the main entrance to the building and all sidewalks abutting the subject property in a clean and sanitary condition in compliance with the Department of Public Works Streets and Sidewalk Maintenance Standards. <i>most unusual, 2010, p. 21, source</i>: a. The Project Sponsor shall be responsible for maintaining the sidewalk within a one-block radius of the Site free of paper or litter generated by the restaurant. b. The Project Sponsor shall maintain the main entrance to the building and all sidewalks abutting the subject property in a clean condition. Such maintenance shall include, at a minimum, daily litter pickup and disposal, and washing or steam cleaning of the main entrance and abutting sidewalks at least once each week. c. . . .
Garbage, Composting and Recycling Storage	<i>early, 2007, p. 20, source</i>: Space for the collection and storage of garbage, composting, and recycling shall be provided within enclosed areas on the property and clearly labeled and illustrated on the architectural addenda. Space for the collection and storage of recyclable and compostable materials that meets the size, location, accessibility and other standards specified by the San Francisco Recycling Program shall be provided at the ground level of the buildings.

Block or heading	Example
Final Materials	<i>typical, 2021, p. 25, source</i>: Space for the collection and storage of garbage, composting, and recycling shall be provided within enclosed areas on the property and clearly labeled and illustrated on the building permit plans. Space for the collection and storage of recyclable and compostable materials that meets the size, location, accessibility and other standards specified by the San Francisco Recycling Program shall be provided at the ground level of the buildings. <i>most unusual, 2020, p. 15, source</i>: Garbage, recycling, and compost containers shall be kept within the premises and hidden from public view, and placed outside only when being serviced by the disposal company. Trash shall be contained and disposed of pursuant to garbage and recycling receptacles guidelines set forth by the Department of Public Works. <i>early, 2010, p. 21, source</i>: The Project Sponsor shall continue to work with Planning Department on the building design. Final materials, glazing, color, texture, landscaping, and detailing shall be subject to Department staff review and approval. The architectural addenda shall be reviewed and approved by the Planning Department prior to issuance. <i>most unusual, 2018, p. 20, source</i>: The Project Sponsor shall continue to work with Planning Department on the building design with respect to the following: a. Limit the massing of the building to a maximum of three-floors. A partial fourth floor setback 15' from the front building wall and incorporating a gabled, hipped or otherwise shaped roof form (with or without dormer windows) may be permitted. a. To comply with the Residential Design Guideline to "Design the scale of the building to be compatible with the ...
Bicycle Parking	<i>early, 2008, p. 22, source</i>: The project shall include secure parking for a minimum of 39 bicycles. The secured bicycle parking shall be provided at the first garage level below street level. Bicycle parking shall be accessible to customers during regular business hours and employees at any time during their hours of employment. Bicycle parking shall be accessible to residents 24 hours a day, 7 days a week. <i>typical, 2020, p. 19, source</i>: The Project shall provide no fewer than six Class 1 bicycle parking spaces as required by Planning Code Sections 155.1 and 155.2. <i>most unusual, 2023, p. 45, source</i>: Pursuant to Planning Code Sections 155, 155.1, and 155.2, the Project shall provide no fewer than 414 bicycle parking spaces (352 Class I spaces and 56 Class II spaces for the residential portion of the Project; and 2 Class I spaces and 4 Class II spaces for the retail portion of the Project). SFMTA has final authority on the type, placement and number of Class II bicycle racks within the public ROW. Prior to issuance of first architectural addenda, the ...
Rooftop Mechanical Equipment	<i>early, 2011, p. 24, source</i>: Pursuant to Planning Code 141, the Project Sponsor shall submit a roof plan to the Planning Department prior to Planning approval of the building permit application. Rooftop mechanical equipment, if any is proposed as part of the Project, is required to be screened so as not to be visible from any point at or below the roof level of the subject building.

Block or heading	Example
Managing Traffic During Construction	<i>most unusual, 2013, p. 43, source</i>: Any rooftop mechanical equipment is required to be screened so as not to be visible from any point at or below the roof level of the subject building. A Roof Plan is incorporated into the plans dated February 22, 2012 (Cathedral Hill Campus MOB) and May 06, 2013 (Cathedral Hill Campus Hospital), and stamped “EXHIBIT B” included in the docket for Case No. 2009.0885C. The final Roof Plans shall be submitted to the Department prior to approval of the Architectural . . . <i>early, 2011, p. 26, source</i>: The Project Sponsor and construction contractor(s) shall coordinate with the Traffic Engineering and Transit Divisions of the San Francisco Municipal Transportation Agency (SFMTA), the Police Department, the Fire Department, the Planning Department, and other construction contractor(s) for any concurrent nearby Projects to manage traffic congestion and pedestrian circulation effects during construction of the Project. <i>most unusual, 2014, p. 17, source</i>: The Project Sponsor and construction contractor(s) shall coordinate with the Traffic Engineering and Transit Divisions of the San Francisco Municipal Transportation Agency (SFMTA), the Police Department, the Fire Department, the Planning Department, and other construction contractor(s) for any concurrent nearby Projects to manage traffic congestion and pedestrian circulation effects during construction of the Project. Prior to commencing construction, the Project Sponsor shall consult with the affected neighbors on Assessor’s Block 105 before finalizing the construction staging and traffic plan, including: . . .
Lighting	<i>early, 2008, p. 16, source</i>: The Applicant shall develop a lighting program for the Project, which shall be subject to review and approval by Preservation staff. The lighting program shall include any lighting required or proposed within the public right-of-way as well as lighting attached to the building. Once approved by Department staff, the lighting program information shall be submitted and approved as part of the first building or site permit for the Project. <i>typical, 2021, p. 35, source</i>: All Project lighting shall be directed onto the Project site and immediately surrounding sidewalk area only, and designed and managed so as not to be a nuisance to adjacent residents. Nighttime lighting shall be the minimum necessary to ensure safety, but shall in no case be directed so as to constitute a nuisance to any surrounding property. <i>most unusual, 2010, p. 37, source</i>: The Project Sponsor shall develop a lighting program for the Project which shall be subject to review and approval by Planning Department staff. The lighting program shall include any lighting required or proposed within the public right-of-way as well as lighting attached to the building. Once approved by Department staff, the lighting program information shall be submitted and approved as part of the first building or site permit for the Project.
Garbage, Recycling, and Composting Receptacles	<i>early, 2007, p. 21, source</i>: Garbage, recycling, and compost containers shall be kept within the premises and hidden from public view, and placed outside only when being serviced by the disposal company. Trash shall be contained and disposed of pursuant to garbage and recycling receptacles guidelines set forth by the Department of Public Works.

Block or heading	Example
Validity and Expiration	<i>most unusual, 2011, p. 21, source</i>: Garbage, recycling, and compost containers shall be kept within the premises and hidden from public view, and placed outside only when being serviced by the disposal company. Trash shall be contained and disposed of pursuant to garbage and recycling receptacles guidelines set forth by the Department of Public Works. 15. Community Liaison. Prior to issuance of a building permit to construct the project and implement the approved use, the Project Sponsor shall appoint a community liaison officer to deal with . . . <i>early, 2007, p. 20, source</i>: The authorization and right vested by virtue of this action is valid for three years from the effective date of the Motion. A building permit from the Department of Building Inspection to construct the project and/or commence the approved use must be issued as this Conditional Use authorization is only an approval of the proposed project and conveys no independent right to construct the project or to commence the approved use. The Planning Commission may, in a public hearing, consider . . . <i>most unusual, 2011, p. 12, source</i>: The authorization and right vested by virtue of this action is valid immediately after motion XXXXX has been finalized.
First Source Hiring	<i>early, 2008, p. 21, source</i>: The project is subject to the requirements of the First Source Hiring Program (Chapter 83 of the Administrative Code) and the Project Sponsor shall comply with the requirements of this Program. <i>typical, 2021, p. 28, source</i>: The Project shall adhere to the requirements of the First Source Hiring Construction and End-Use Employment Program approved by the First Source Hiring Administrator, pursuant to Section 83.4(m) of the Administrative Code. The Project Sponsor shall comply with the requirements of this Program regarding construction work and on-going employment required for the Project. <i>most unusual, 2025, p. 27, source</i>: The Project shall adhere to the First Source Hiring requirements set forth in Exhibit I of the Development Agreement.
Signage	<i>early, 2008, p. 16, source</i>: The Applicant shall develop a signage program for the Project, which shall be subject to review and approval by Preservation staff. All subsequent sign permits shall conform to the approved signage program. Once approved by the Department, the signage program information shall be submitted and approved as part of the first building or site permit for the Project. No general advertising signs shall be permitted anywhere on the building. <i>typical, 2012, p. 33, source</i>: The Project Sponsor shall develop a signage program for the Project which shall be subject to review and approval by Planning Department staff before submitting any building permits for construction of the Project. All subsequent sign permits shall conform to the approved signage program. Once approved by the Department, the signage program/plan information shall be submitted and approved as part of the site permit for the Project. All exterior signage shall be designed to compliment, not compete with, the existing . . . <i>most unusual, 2011, p. 15, source</i>: The “Discolandia” sign shall be preserved.
Parking Maximum	<i>early, 2011, p. 26, source</i>: Pursuant to Planning Code Section 151.1, the Project shall provide no more than 35 independently accessible off-street parking spaces, excluding car share spaces.

Block or heading	Example
Monitoring	<i>typical, 2020, p. 19, source</i>: Pursuant to Planning Code Section 151, the Project shall provide no more than nine (9) off-street parking spaces. <i>most unusual, 2025, p. 21, source</i>: The Tower shall provide no more off-street parking spaces than permitted by Applicable Laws (as that term is defined in the Development Agreement). The parking area for the New Fire Station shall not be materially increased, unless a greater number is permitted pursuant to Planning Code Section 151 or 151.1. <i>early, 2009, p. 62, source</i>: If the project requires monitoring of the conditions of approval contained in Exhibit A of Motion No. 17955, the project sponsor or the subsequent responsible parties for the project shall pay fees as established under Planning Code Section 351(e)(1) and work with the Planning Department to ensure compliance. <i>typical, 2021, p. 56, source</i>: The Project requires monitoring of the conditions of approval in this Motion. The Project Sponsor or the subsequent responsible parties for the Project shall pay fees as established under Planning Code Section 351(e) (1) and work with the Planning Department for information about compliance. <i>most unusual, 2011, p. 20, source</i>: Prior to demolition, excavation and construction activity, the project sponsor shall hire a structural engineer specializing in historical structures to perform an initial existing condition survey of the California Club of California at 1748-1750 Clay Street (Block 0619, Lot 008) to establish a baseline of existing damage/cracks. The structural engineer shall monitor the existing damage/cracks periodically during construction. The initial existing condition survey and monitoring reports shall be copied to the Zoning Administrator for reference and for inclusion in the ...
Additional Project Authorization	<i>early, 2012, p. 40, source</i>: The Project Sponsor must obtain a Project authorization under Sections 320 through 325 to allocate office square footage, as well as findings under Section 295 as to whether the shadow cast by the project on Union Square would have an adverse impact to the park. The conditions set forth below are additional conditions required in connection with the Project. If these conditions overlap with any other requirement imposed on the Project, the more restrictive or protective condition or requirement, as ... <i>typical, 2021, p. 16, source</i>: The Project Sponsor shall obtain operating licenses from the City's Office of Cannabis and the State of California prior to commencing any cannabis sales or other activities per Planning Code Section 202.2(a)(5). <i>most unusual, 2018, p. 32, source</i>: The Project Sponsor must obtain a Shadow Determination under Section 295 that the net new shadow cast by the Project on the proposed 11th and Natoma Park will be insignificant to the use of the park, a Variance under Section 305 from Planning Code requirements for Awning Obstructions (Section 136.1), Dwelling Unit Exposure (Section 140), and Ground Floor Ceiling Height (Section 145.1(c)(4)), a Rear Yard Modification (Section 134(e)(1)), and an Elevator Height Exemption Waiver (Section 260(b)(1)(B)), and satisfy all the ...

Block or heading	Example
Mitigation Measures	<i>early, 2001, p. 28, source</i>: The Project shall be subject to, and the Project Sponsor shall implement and otherwise comply with, the Mitigation Measures proposed as part of the Project, as outlined in the Project's FND (Case No. 2000.1215BEKX), included as Condition of Approval 2.A. of the Section 309 Motion (Motion No. -----, Case No. 2000.1215BEKX) for the Project (Case No. 2000.1215BEKX), and incorporated herein by this reference. <i>typical, 2013, p. 31, source</i>: Mitigation measures described in the MMRP attached as Exhibit C are necessary to avoid potential significant effects of the proposed project and have been agreed to by the project sponsor. Their implementation is a condition of project approval. <i>most unusual, 2014, p. 68, source</i>: Diesel Emissions Control Strategy (VDECS).
Transportation Sustainability Fee	<i>early, 2016, p. 41, source</i>: The project is subject to the Transportation Sustainability Fee (TSF), as applicable, pursuant to Planning Code Section 411A. <i>most unusual, 2018, p. 31, source</i>: Pursuant to Planning Code Section 411A, the Project shall pay for the residential uses within the Project, either: i) pay \$3.87 per gross square foot (approximately equal to 50% of the TSF applicable to residential uses); or ii) comply with the TSF, if applicable to the project, whichever calculation results in a higher TSF requirement. Non-residential or PDR uses would continue to be subject to the TIDF at the rate applicable per Planning Code Sections 411.3(e) and 409, as well ...
Residential Child Care Impact Fee	<i>early, 2016, p. 40, source</i>: Pursuant to Planning Code Section 414A, the Project Sponsor shall pay the Residential Child Care Impact Fee, as required by and based on drawings submitted with the Building Permit Application. The Project Sponsor shall pay the fee at the time of and in no event later than the issuance of the First Construction Document. <i>typical, 2021, p. 28, source</i>: The Project is subject to the Residential Child Care Fee, as applicable, pursuant to Planning Code Section 414A.
Streetscape Plan	<i>early, 2011, p. 25, source</i>: Pursuant to Planning Code Section 138.1, the Project Sponsor shall submit a pedestrian streetscape improvement plan to the Planning Department for review in consultation with the Department of Public Works and the Department of Parking and Traffic prior to Building Permit issuance. <i>typical, 2021, p. 25, source</i>: Pursuant to Planning Code Section 138.1, the Project Sponsor shall continue to work with Planning Department staff, in consultation with other City agencies, to refine the design and programming of the Streetscape Plan so that the plan generally meets the standards of the Better Streets Plan and all applicable City standards. The Project Sponsor shall complete final design of all required street improvements, including procurement of relevant City permits, prior to issuance of first architectural addenda, and shall complete construction ... <i>most unusual, 2019, p. 44, source</i>: The Development Agreement (Board File No. 190845) provides for certain streetscape improvements to be constructed and dictates the timing of such construction. In addition, the Project Sponsor is seeking approval of a major encroachment permit in connection with certain proposed streetscape improvements located in the public right of way, including new and replacement street trees and trees to replace certain existing significant trees (MEP). Pursuant to the applicable provisions of the Development Agreement and the MEP, the Project Sponsor shall ...

Block or heading	Example
Noise Control	<i>early, 2010, p. 21, source</i>: The noise shall be adequately soundproofed or insulated for noise and operated so that incidental noise shall not be audible beyond the premises or in other sections of the building and fixed-source equipment noise shall not exceed the decibel levels specified in the San Francisco Noise Control Ordinance. <i>typical, 2012, p. 15, source</i>: The premises shall be adequately soundproofed or insulated for noise and operated so that incidental noise shall not be audible beyond the premises or in other sections of the building and fixed-source equipment noise shall not exceed the decibel levels specified in the San Francisco Noise Control Ordinance. <i>most unusual, 2010, p. 22, source</i>: The Project Sponsor shall operate the proposed restaurant such that noise is kept at reasonable levels so as not to unduly disturb neighboring residents and businesses. Any new ductwork shall not discharge near residential window openings or obscure any windows.
Hours of Operation	<i>early, 2008, p. 23, source</i>: The hours of operation for the proposed grocery store at the project site will be limited to the hours of 8:00 a.m. to 10:00 p.m. These hours may fluctuate a few days prior to public holidays such as Thanksgiving and Christmas. The project sponsor or the retail tenant may seek extension of the hours (outside of major holidays) if it is determined that there is sufficient demand, need and desire in the neighborhood for additional hours of operation, and such . . . <i>typical, 2013, p. 17, source</i>: The subject establishment is limited to the following hours of operation: 6:00 a.m. to 10:00 p.m. daily. <i>most unusual, 2013, p. 14, source</i>: Condition 1(K) of Motion 17592 is revoked. The ground-floor commercial space may operate 24-hours per day, 7 days per week. The retail sales and pharmacy are to be open at the same time so there is no period when one is open and one is closed.
Transportation Demand Management (TDM) Program	<i>early, 2017, p. 32, source</i>: The Project shall be subject to the recently adopted TDM Program upon the effective date of Ordinance No. 222-15, specifically Section 169 et seq. and the associated TDM Program Standards, as adopted by the Planning Commission and periodically amended. <i>typical, 2021, p. 26, source</i>: Pursuant to Planning Code Section 169, the Project shall finalize a TDM Plan prior to the issuance of the first Building Permit or Site Permit to construct the project and/or commence the approved uses. The Property Owner, and all successors, shall ensure ongoing compliance with the TDM Program for the life of the Project, which may include providing a TDM Coordinator, providing access to City staff for site inspections, submitting appropriate documentation, paying application fees associated with required monitoring and . . . <i>most unusual, 2017, p. 105, source</i>: The Project shall be subject to the recently adopted TDM Program upon the effective date of Ordinance No. 222-15, specifically Section 169 et seq. and the associated TDM Program Standards, as adopted by the Planning Commission and periodically amended. The two (2) additional car-share spaces above the maximum of six (6) permitted for this Project shall be allowed only on the condition they are provided to meet the minimum requirements of the TDM Program.

Block or heading	Example
Noise	<i>early, 2010, p. 21, source:</i> , Ambient. Interior occupiable spaces shall be insulated from ambient noise levels. Specifically, in areas identified by the Environmental Protection Element, Map1, “Background Noise Levels,” of the General Plan that exceed the thresholds of Article 29 in the Police Code, new developments shall install and maintain glazing rated to a level that insulate interior occupiable areas from Background Noise and comply with Title 24. <i>typical, 2019, p. 30, source:</i> Plans submitted with the building permit application for the approved project shall incorporate acoustical insulation and other sound proofing measures to control noise. <i>most unusual, 2010, p. 43, source:</i> 35
Odor Control Unit	<i>early, 2010, p. 21, source:</i> The plans submitted with the building permit application for the approved Project shall incorporate odor control ducting shall not be applied to the primary facade of the building. <i>typical, 2020, p. 20, source:</i> In order to ensure any significant noxious or offensive odors are prevented from escaping the premises once the project is operational, the building permit application to implement the project shall include air cleaning or odor control equipment details and manufacturer specifications on the plans. Odor control ducting shall not be applied to the primary facade of the building.
Transformer Vault	<i>early, 2011, p. 24, source:</i> The location of individual project PG&E Transformer Vault installations has significant effects to San Francisco streetscapes when improperly located. However, they may not have any impact if they are installed in preferred locations. Therefore, the Planning Department recommends the following preference schedule in locating new transformer vaults, in order of most to least desirable: 1. On-site, in a basement area accessed via a garage or other access point without use of separate doors on a ground floor facade facing a ... <i>typical, 2019, p. 29, source:</i> The location of individual project PG&E Transformer Vault installations has significant effects to San Francisco streetscapes when improperly located. However, they may not have any impact if they are installed in preferred locations. Therefore, the Planning Department recommends the following preference schedule in locating new transformer vaults, in order of most to least desirable: A. On-site, in a basement area accessed via a garage or other access point without use of separate doors on a ground floor facade facing a ... <i>most unusual, 2019, p. 15, source:</i> The location of individual project PG&E Transformer Vault installations has significant effects to San Francisco streetscapes when improperly located. However, they may not have any impact if they are installed in preferred locations. Therefore, the Planning Department recommends the following preference schedule in locating new transformer vaults: The Planning Department does not support installing transformers within the public ROW at this location. The project shall locate all electrical transformers required to service the property on the private property within transformer ...
Overhead Wiring	<i>early, 2011, p. 25, source:</i> The Property owner will allow MUNI to install eyebolts in the building adjacent to its electric streetcar line to support its overhead wire system if requested by MUNI or MTA.

Block or heading	Example
Eastern Neighborhoods Infrastructure Impact Fee	<i>most unusual, 2015, p. 124, source</i>: The Property owner will allow MUNI to install eyebolts in the building adjacent to its electric streetcar line to support its overhead wire system if requested by MUNI or MTA. Noise, Ambient. Interior occupiable spaces shall be insulated from ambient noise levels. Specifically, in areas identified by the Environmental Protection Element, Map 1, “Background Noise Levels,” of the General Plan that exceed the thresholds of Article 29 in the Police Code, new developments shall install and maintain glazing rated to . . . <i>early, 2011, p. 37, source</i>: Pursuant to Planning Code Section 423 (formerly 327), the Project Sponsor shall comply with the Eastern Neighborhoods Public Benefit Fund provisions through payment of an Impact Fee pursuant to Article 4. <i>typical, 2021, p. 28, source</i>: The Project is subject to the Eastern Neighborhoods Infrastructure Impact Fee, as applicable, pursuant to Planning Code Section 423. <i>most unusual, 2013, p. 30, source</i>: Pursuant to Planning Code Section 423 (formerly 327), the Project Sponsor shall comply with the Eastern Neighborhoods Public Benefit Fund provisions through payment of an Impact Fee pursuant to Article 4 of the Planning Code and/or through an In-Kind Agreement, as approved by the Planning Commission.
Anti-Discriminatory Housing	<i>early, 2016, p. 40, source</i>: The Project shall adhere to the requirements of the Anti- Discriminatory Housing policy, pursuant to Administrative Code Section 1.61. <i>most unusual, 2020, p. 22, source</i>: The Project shall adhere to the requirements of the Anti- Discriminatory Housing policy, pursuant to Administrative Code Section 1.61. www.sf-planning.org 11. Inclusionary Affordable Housing Program and California Density Bonus Law for Student Housing. Pursuant to Planning Code Section 415.3(f)(5), the Affordable Housing Program does not apply to student housing projects that meet certain criteria, provided that the Project Sponsor shall comply with the requirements set forth in the Student Housing and MOH Monitoring Fee condition . Instead, per California Government . . .
Car Share	<i>early, 2011, p. 26, source</i>: Pursuant to Planning Code Section 166, no fewer than one car share space shall be made available, at no cost, to a certified car share organization for the purposes of providing car share services for its service subscribers. <i>typical, 2021, p. 27, source</i>: Pursuant to Planning Code Section 166, no fewer than one (1) car share space shall be made available, at no cost, to a certified car share organization for the purposes of providing car share services for its service subscribers. <i>most unusual, 2025, p. 21, source</i>: There is no car share requirement applicable to the Project.
Lighting Plan	<i>early, 2011, p. 24, source</i>: The Project Sponsor shall submit an exterior lighting plan to the Planning Department prior to Planning Department approval of the building / site permit application.

Block or heading	Example
Eating and Drinking Uses	<i>most unusual, 2019, p. 130, source:</i> For all properties that are considered historic resources under CEQA, or Articles 10 or 11 of the Planning Code, the Project Sponsor shall submit additional details in the building permit applications regarding the proposed lighting, which shall be subject to Department staff review and approval in substantial conformance with the plan sets in Exhibit B. This final review and approval may include, but is not limited to, the type and location of light fixtures, means of attachment, methods of conduit . . . <i>early, 2017, p. 21, source:</i> As defined in Planning Code Section 202.2, Eating and Drinking Uses, as defined in Section 102, shall be subject to the following conditions: A. The business operator shall maintain the main entrance to the building and all sidewalks abutting the subject property in a clean and sanitary condition in compliance with the Department of Public Works Street and Sidewalk Maintenance Standards. In addition, the operator shall be responsible for daily monitoring of the sidewalk within a one-block radius of the . . . <i>most unusual, 2018, p. 33, source:</i> As defined in Planning Code Section 202.2, Eating and Drinking Uses, as shall be subject to the following conditions: defined in Section J1 snN F~aNcisco 33 a. The business operator shall maintain the main entrance to the building and all sidewalks abutting the subject property in a clean and sanitary condition in compliance with the Department of Public Works Street and Sidewalk Maintenance Standards. In addition, the operator shall be responsible for daily monitoring of the sidewalk within a one-block radius . . .
Compatibility with City Emergency Services – WTS	<i>early, 2011, p. 22, source:</i> The facility shall not be operated or caused to transmit on or adjacent to any radio frequencies licensed to the City for emergency telecommunication services such that the City’s emergency telecommunications system experiences interference, unless prior approval for such has been granted in writing by the City. <i>most unusual, 2011, p. 56, source:</i> The facility shall not be operated or caused to transmit on or adjacent to any radio frequencies licensed to the City for emergency telecommunication services such that the City’s emergency telecommunications system experiences interference, unless prior approval for such has been granted in writing by the City. > Let me know if you have any questions. I am happy to discuss each > proposed condition with you. > > Thanks Marc > — On Tue, 5/3/11, Richard.Sucre@sfgov.org <Richard.Sucre@sfgov.org> wrote: > . . .
Installation - WTS	<i>early, 2011, p. 21, source:</i> Within 10 days of the installation and operation of the facilities, the Project Sponsor shall confirm in writing to the Zoning Administrator that the facilities are being maintained and operated in compliance with applicable Building, Electrical and other Code requirements, as well as applicable FCC emissions standards. <i>most unusual, 2018, p. 16, source:</i> Within 10 days of the installation and operation of the facilities, the Project Sponsor shall confirm in writing to the Zoning Administrator that the facilities are being maintained and operated in compliance with applicable Building, Electrical and other Code requirements, as well as applicable FCC emissions standards. 16

Wording drift. Table 14 compares, for each frequent heading with enough bodies in two or more eras, the most common body in the first era it appears and in the last, on number-masked text. Of the 40 headings compared, 26 kept the same most common sentence from the first era to the last (a

similarity of at least 0.99). 9 were rewritten — a similarity below 0.60 — and they are the rows at the top of the table: Additional Project Authorization; Residential Child Care Impact Fee; Eastern Neighborhoods Infrastructure Impact Fee; Lighting; Mitigation Measures; Noise; Extension; Hours of Operation; Community Liaison. For most of them the lowest similarity between adjacent eras is as low as that between the first era and the last: the sentence was replaced at one step rather than drifting.

Table 14: Wording drift. For each frequent heading with at least five bodies in two or more eras, the similarity (0–1, on number-masked text) of its most common body in the first and last era it appears in, and the lowest similarity between adjacent eras. 1 means the template did not change.

Heading	First era	Last era	First vs last	Lowest adjacent
Additional Project Authorization	2011–2014	2022–2026	0.12	0.26
Residential Child Care Impact Fee	2015–2017	2022–2026	0.17	0.17
Eastern Neighborhoods Infrastructure Impact Fee	2011–2014	2022–2026	0.22	0.22
Lighting	2010	2022–2026	0.25	0.25
Mitigation Measures	2010	2022–2026	0.27	0.27
Noise	2010	2022–2026	0.28	0.28
Extension	2011–2014	2022–2026	0.45	0.45
Hours of Operation	2011–2014	2022–2026	0.47	0.47
Community Liaison	2003–2009	2022–2026	0.49	0.48
First Source Hiring	2010	2022–2026	0.64	0.64
Signage	2010	2022–2026	0.73	0.16
Enforcement	2010	2022–2026	0.86	0.86
Monitoring	2010	2022–2026	0.90	0.91
Garbage, Composting and Recycling Storage	2011–2014	2022–2026	0.96	0.96
Parking Maximum	2011–2014	2022–2026	0.99	0.99
Transformer Vault	2011–2014	2018–2021	0.99	0.99
Revocation due to Violation of Conditions	2011–2014	2022–2026	1.00	1.00
Conformity with Current Law	2011–2014	2022–2026	1.00	1.00
Validity	2011–2014	2022–2026	1.00	1.00
Expiration and Renewal	2011–2014	2022–2026	1.00	1.00
Diligent Pursuit	2011–2014	2022–2026	1.00	1.00
Sidewalk Maintenance	2011–2014	2022–2026	1.00	1.00
Final Materials	2011–2014	2022–2026	1.00	1.00
Bicycle Parking	2011–2014	2022–2026	1.00	1.00
Rooftop Mechanical Equipment	2011–2014	2022–2026	1.00	1.00
Managing Traffic During Construction	2011–2014	2022–2026	1.00	1.00
Garbage, Recycling, and Composting Receptacles	2011–2014	2018–2021	1.00	1.00
Validity and Expiration	2011–2014	2018–2021	1.00	1.00
Transportation Sustainability Fee	2015–2017	2022–2026	1.00	1.00
Streetscape Plan	2011–2014	2022–2026	1.00	1.00
Noise Control	2011–2014	2022–2026	1.00	1.00
Transportation Demand Management (TDM) Program	2015–2017	2022–2026	1.00	1.00
Odor Control Unit	2011–2014	2022–2026	1.00	1.00
Overhead Wiring	2011–2014	2022–2026	1.00	1.00
Anti-Discriminatory Housing	2015–2017	2022–2026	1.00	1.00
Car Share	2011–2014	2022–2026	1.00	1.00
Lighting Plan	2011–2014	2022–2026	1.00	1.00
Eating and Drinking Uses	2015–2017	2022–2026	1.00	1.00
Compatibility with City Emergency Services – WTS	2011–2014	2022–2026	1.00	1.00
Installation - WTS	47	2022–2026	1.00	1.00

4 The long tail

642 of the 1,383 distinct headings occur in one motion only. Table 15 quotes 20 of those conditions, drawn at random with a fixed seed, with the kind of case each belongs to. These are the conditions a coding scheme will not anticipate, and they are where the Commission’s attention to the particular site shows. A count of them per motion would be a cleaner measure of bespoke conditioning than the total. The draw is from headings seen once, so a condition whose heading is common but whose body is not is not in it; some drawn rows are also parser artefacts (a heading read from the first words of a sentence), which is what a random draw of one-offs is expected to surface.

Table 15: The long tail: 20 conditions whose heading appears in no other motion, drawn at random (seed fixed), with the kind of case they belong to.

Heading	Case type	Body
Geology/Topography	conditional use	The potential liquefaction hazard on the project site would be the same under the Revised Project as it would under the Original Project. This hazard would be avoided through the implementation of the California Division of Mines and Geology (CDMG) existing requirement for a geotechnical report, the SF Department of Building Inspection (DBI) review of the building permit applications and plans, and incorporation of seismic safety measures of the Planning Code or seismic safety requirements specified by DBI. The Project ... (2005, p. 60, source)
Trash	downtown project	Trash receptacles and dumpsters shall not be stored on public property or in project common space, and they shall be screened from public view. (2006, p. 51, source)
Residential Demolition (Planning Code Section 726.38)	conditional use	Demolition of Existing Residential Building by Conditional Use. The following variances are also requested: Rear Yard Modification under Planning Code Section 134(e)1 states that "The rear yard requirement in NC Districts may be modified or waived by the Zoning Administrator pursuant to the procedures which are applicable to variances." (Valencia Street Neighborhood Commercial District - Planning Code Section 726.12 mentions 25% Rear Yard required at the Second Story and above and at all residential levels. Adjacent south property has ... (2010, p. 43, source)
MITIGATION MEASURES AND IMPROVEMENT MEASURES ... 81	conditional use	Mitigation Measure 1: Archeological Resources (Archeological Testing) ... 81 Mitigation Measure 2: Construction Noise (Pile Driving) ... 84 Mitigation Measure 3: Construction Noise (Pile Driving) ... 85 Mitigation Measure 4: Hazards (Contaminated Soil) ... 85 Mitigation Measure 5: Other Hazardous Building Materials (PCBs, Mercury, Lead, and others) ... 86 Mitigation Measure 6: Paleontological Resources ... 86 (2012, p. 26, source)

Heading	Case type	Body
Signage – Intensity of Lighting	conditional use	The Project Sponsor shall continue to work with Planning Department staff to ensure a reasonable intensity of internal and external lighting for signage and other features visible from the street. The Project Sponsor shall make an informational presentation on the internal and external lighting plan for the project once the Planning Department approves the associated sign permit(s). (2013, p. 11, source)
Archeological Monitoring Program	conditional use	If the ERO in consultation with the archeological consultant Project sponsor/ AMP required? archeological Project sponsor/ determines that an archeological monitoring program shall be implemented the archeological archeological Y/N consultant archeological monitoring program shall minimally include the following provisions: consultant/ Date:----- shall meet consultant/ • The archeological consultant, project sponsor, and ERO shall meet and consult on the scope archeological monitor/ -- prior to archeological of the AMP reasonably prior to any project-related soils disturbing activities commencing. The ERO contractor(s), ... (2014, p. 34, source)
Bicycle Parking (Convention Center)	not in the item table	Pursuant to Planning Code Section 155.1, the Zoning Administrator has determined that the Project shall provide no fewer than 18 Class 1 and 50 Class 2 bicycle parking spaces. The Class 2 facilities shall be periodically monitored and their usage shall be reported annually to the Zoning Administrator. The Zoning Administrator will use this information to determine the adequacy of the Class 2 bicycle parking provided on the site, and may adjust the Class bicycle parking requirement based on this ... (2014, p. 89, source)
Eastern Neighborhoods Mixed-Use Usable Open Space In Lieu Fee	office allocation	Pursuant to Planning Code Section 426, in Eastern Neighborhoods Mixed Use Districts, the open space requirement for non- residential requirements shall be satisfied through payment of a fee in accordance with Article 4. (2015, p. 21, source)
J-1	large project authorization	Properties with Previous Not Applicable: project site does N/A Studies not contain any previous archaeological studies J-2: Properties with no Previous Applicable: project site is located in The project sponsor has agreed Studies an area with no previous to implement the Planning archaeological studies Department’s Standard Mitigation Measure #1 (Accidental Discovery). J-3: Mission Dolores Not Applicable: project site is not N/A Archeological District located within the Mission Dolores Archaeological District (2016, p. 44, source)

Heading	Case type	Body
Recycling Plan	conditional use	The Project shall develop a recycling plan. Space for the collection and storage of recycling shall be provided within enclosed areas on the property and clearly labeled and illustrated on the building permit plans. Space for the collection and storage of recyclable materials that meets the size, location, accessibility and other standards specified by the San Francisco Recycling Program shall be provided at the ground level of the buildings. <i>(2017, p. 16, source)</i>
Mitigation for Nested Bedrooms	downtown project	At the direction of the Planning Commission and in order to minimize the number of units with a nested bedroom configuration, the project shall provide fire-rated property line windows along the southern side property line for those 1-bedroom units that are located vertically above the adjacent building at 129 Hyde Street. <i>(2018, p. 28, source)</i>
4, Minimum Unit Sizes	conditional use	The affordable units shall meet the minimum unit sizes standards established by the California Tax Credit Allocation Committee (TCAC) as of May 16, 2017. One-bedroom units must be at least 450 square feet, two-bedroom units must be at least 700 square feet, and three-bedroom units must be at least 900 square feet. Studio units must be at least 300 square feet pursuant to Planning Code Section 415.6(f)(2). The total residential floor area devoted to the affordable units ... <i>(2019, p. 25, source)</i>
Commission Conditions	conditional use	During the Planning Commission hearing, the Commission conditioned the project to the following design changes: A. Provide separate entries; B. Reduce the rear deck; and C. Improve access to light and livability to the lower unit. <i>(2019, p. 17, source)</i>
BB	large project authorization	Streetscape Plan. Pursuant to Planning Code Section 138.1, the Project Sponsor shall continue to work with Planning Department staff, in consultation with other City agencies, to refine the design and programming of the Streetscape Plan so that the plan generally meets the standards of the Better Streets Plan and all applicable City standards. The Project Sponsor shall complete final design of all required street improvements, including procurement of relevant City permits, prior to issuance of first architectural addenda, and shall ... <i>(2020, p. 26, source)</i>
Roof Deck and Lightwell	conditional use	The Project Sponsor shall continue to work with the adjacent properties on the project impact, especially for the roof deck and lightwell design to enhance security and minimize the impact on the neighbor's property line windows. <i>(2020, p. 19, source)</i>

Heading	Case type	Body
Consumption Lounge Ventilation	conditional use	The rear windows of the on-site consumption lounge shall be inoperable and remain closed during business hours and/or operations. The windows shall be sufficiently sealed to comply with Department of Public Health ventilation standards for consumption lounges and to prevent any smoke or odor from escaping into the rear yard. (2021, p. 15, source)
Relinquishment of Office Allocation	office allocation	The Project Sponsor may relinquish all or a portion of the 896,323 square feet of Office Allocation use in writing to the Zoning Administrator, which would become effective upon the Zoning Administrator's issuance of such a written determination. In the event of such relinquishment, the Large Cap shall be appropriately adjusted and the number of required New Affordable Housing Units shall be reduced on a pro rata basis. (2021, p. 23, source)
Storage Area	conditional use	The applicant shall work with staff on the appropriate design solution for replacement of the garage door and to allow the space to be used as storage. (2022, p. 14, source)
Department-Facilitated Community Meeting	conditional use	Prior to the end of calendar year 2023, Planning Department staff shall facilitate a meeting among the community groups, the cultural district and the Project Sponsor toward developing a "good neighbor" policy among the parties. (2023, p. 23, source)
(Department Intent to Create CEBA)	other	In order to more efficiently implement the provisions of Section 164, the Department is encouraging the creation of a Central Employment Brokerage Association (CEBA) to provide services required under Section 164 to Project Sponsors subject to Section 164, among others. (2024, p. 84, source)

5 Counts as a variable

A motion's condition count is the simplest measure of stringency the census makes available, and nothing in the item table can compute it. Table 16 and Figure 2 give it by hearing year for adopted motions (numbered or named conditions only; the 5 preamble blocks are excluded because every modern motion has them), beside the share of items the item table flags as conditioned. The median adopted motion carries 14 conditions (mean 15.9). Across the 18 years with at least 10 motions read, the rank correlation between the median count and the conditioning share is -0.22: **the count is not rising with the conditioning share**. Read with the corpus memo's substitution — denial falling, conditioning rising — that says the rise is in how often the Commission conditions, more than in how much each approval carries.




Figure 2: Conditions per adopted motion (median and interquartile band) by hearing year, beside the share of items the item table flags as conditioned.

Table 17 splits the count by the case's request type and by project scale. The count rises with scale: the median motion for a project that adds no units carries 13 conditions, against 28 for the 348 motions in the largest unit band, and the large-project authorisations carry the most of any request type.

Table 16: Conditions per motion (numbered or named conditions only, standing preamble blocks excluded), adopted motions by hearing year (years with at least 10 motions), beside the share of items the item table flags as conditioned.

Year	Motions	Median	p25	p75	Items conditioned
2001	11	11	8	16	21.8%
2008	69	12	10	18	19.6%
2010	105	17	12	21	24.7%
2011	119	13	9	19	26.1%
2012	98	11	8	19	29.2%
2013	153	14	10	19	38.0%
2014	83	13	10	19	35.3%
2016	11	30	12	34	26.9%
2017	22	20	12	26	25.7%
2018	146	16	12	24	28.9%
2019	150	14	11	17	33.2%
2020	102	13	11	23	27.6%
2021	150	15	13	20	35.5%
2022	65	16	11	23	32.5%
2023	164	12	11	16	45.1%
2024	115	11	9	15	34.9%
2025	104	10	9	14	35.8%
2026	15	10	10	15	30.6%

Table 17: Conditions per motion by the case’s request type and by project scale (proposed units from the Planning Projects table, reached through the case stem). Adopted and draft motions pooled; one row per motion section.

By	Group	Motions	Median	Mean
request type	(not in the item table)	458	13	16.2
request type	ceqa environmental	21	22	21.9
request type	conditional use	2,958	13	14.9
request type	conditional use modification	90	12	12.9
request type	downtown project	101	29	26.9
request type	informational	12	33	34.2
request type	large project authorization	179	31	32.8
request type	office allocation	124	11	12.6
request type	other	27	22	20.8
request type	variance	53	14	16.0
proposed units	0	2,438	13	14.4
proposed units	1	158	13	12.9
proposed units	2–9	413	15	14.9
proposed units	10–49	226	23	23.0
proposed units	50+	348	28	26.6
proposed units	unknown	467	13	16.5

6 Draft against adopted

The packet carries the draft motion; the Commission adopts a motion that may differ. Where the census has both for a case — the latest draft heard on or before the adoption, and the adopted motion — Table 18 matches their conditions: by heading where both carry headings, allowing for OCR in the adopted copy, and then what is left by number-masked text (in 52 pairs the drafts carry no headings and text is the only key). The adopted copy is often a signed scan read by OCR, so a condition whose text differs by a misread letter or a touched-up word is *near-identical*, not changed; only a condition less than 90% similar to the draft's counts as reworded. Of 1,308 pairs, 466 (36%) differ in some condition. Of the 20,856 conditions in the drafts, 18,013 are carried word for word and 1,610 near-identical — 94% in all — 416 are reworded and 817 dropped, and the adopted motions carry 910 conditions the drafts did not.

What the additions are. A condition the adopted motion carries and the draft does not is not necessarily one the Commission added from the dais. Many are the template's standing conditions — Revocation, Noise Control, Managing Traffic During Construction, an odor-control unit, an area-plan fee — which are more plausibly staff completing the draft between the packet and adoption, or conditions the parse missed on the draft side, than Commission action. The table therefore splits them: an addition is *template text* when its opening 200 characters, numbers masked, recur in the motions of at least 10 other cases. 402 of the 910 additions are template text and 508 are not. Table 19 quotes a random draw of the latter; even those mix the Commission's changes with staff's, and nothing in the documents says which is which.

The lower panel crosses the change with the item table's record of the hearing. The item table records modifications for 230 of the pairs, and in 191 of those the conditions did change. It records none for 248 pairs whose conditions changed nonetheless — 232 of them with a change beyond template additions (a condition reworded or dropped, or a non-template one added). **The draft is a good proxy for most of the adopted text.** What the comparison does not establish is that the `modifications` field misses the Commission's own changes: the changes it does not record are partly the Commission's and partly staff completing the draft, and the documents cannot separate the two.

Table 18: Draft against adopted, for every case with both a draft motion and the adopted motion. Conditions are matched by heading where both carry headings (allowing for OCR in the adopted copy), and what is left by text. ‘Reworded’ is a matched condition whose number-masked text is less than 90% similar to the draft’s; ‘near-identical’ differs by less — OCR, typography, a touched-up word — and is not counted as a change. An added condition is ‘template text’ when its opening 200 characters, numbers masked, recur in the motions of at least 10 other cases. The lower panel crosses the change with the item table’s record of the hearing, counting any change (reworded, removed or added) and a change beyond template additions.

Quantity	Value	
Draft–adopted pairs	1,308	
with any change	466 (36%)	
Conditions in the drafts	20,856	
carried word for word	18,013	
carried near-identical	1,610	
reworded	416	
removed	817	
Conditions in the adopted motion, not the draft	910	
template text	402	
other text	508	
	Change beyond	
	Any change	template additions
Item records modifications	191	188
No modifications recorded	248	232
No item at that hearing	27	24

Table 19: Conditions the adopted motion carries and the draft did not, drawn at random from the 508 whose text is not template text (Table 18). Some are the Commission’s changes; some are staff completing the draft, or conditions the parse missed on the draft side — the table cannot tell which.

Case	Added condition
2012.0547C (2012)	<i>Gross Receipts.</i> The Project Sponsor shall submit records of the gross receipts of the restaurant annually, and such records shall distinguish between food sales and alcoholic beverage sales. These records shall be submitted to the Planning Department annually, on or before July 19 of each year, beginning on July 19, 2013. (source)
2013.0224C (2013)	<i>Rooftop Mechanical Equipment Enclosure.</i> The Project Sponsor shall install a rooftop mechanical equipment enclosure, after servicing, to minimize noise transmission. (source)
2015-001360CUA (2017)	<i>Commission Amended.</i> Dwelling units on the corner shall have the floor plans reconfigured so that the bedrooms are not located on the corner bay window area. File No. 2015-001360ENV County of San Francisco maintained by the California Native American Heritage Commission and in the case of the Overseas Chinese, the Chinese Historical Society of America. An appropriate 2 An "appropriate representative" of ... (source)
2014.0376CUA (2018)	<i>Bicycle Parking.</i> Pursuant to Planning Code Sections 155.2, the Project shall provide no fewer than 90 bicycle parking spaces (76 Class 1 spaces for the residential portion of the Project and 14 Class 2 spaces for both the residential and commercial/PDR portion of the Project). (source)
2017-009635CUA (2019)	<i>Noise Control Plan.</i> The Project Sponsor shall incorporate a Noise Control Plan, which includes the following: a. After consultation between the Project Sponsor’s contractor and the Department of Building Inspection, the Project Sponsor shall require that equipment (including trucks) used for project construction have appropriate noise control technology (e.g., improved mufflers, equipment redesign, intake silencers, ducts, engine enclosures, acoustically attenuating shields or shrouds); ... (source)
2018-002060CUA (2019)	<i>untitled.</i> The Flore Store shall provide on-site security personnel to monitor the front of the store and 700 feet adjacent during all hours the store is open, plus 30 minutes before opening and 30 minutes after closing, and provide 24/7/365 day video surveillance of these areas, with recorded video retained for a minimum of 90 days and made available to law ... (source)
2017-016520CUA (2019)	<i>Final Design.</i> To preserve and enhance the compatibility of the proposed Project with the existing neighborhood character, the Commission will require the following modifications to the Project prior to building permit approval: A. The Project’s lightwell along the southern property line shall be expanded to match the width of the adjacent neighbor’s lightwell. B. The roof deck shall be modified in compliance ... (source)
2016-003994CUA (2019)	<i>Furnished Units.</i> No more than two units may be rented as furnished units at any one time. This conditional shall no longer apply if the project is converted to a condominium/ownership project. (source)

Case	Added condition
2018-008661ENX (2020)	<i>Neighborhood Organization Coordination.</i> The Project Sponsor is required to work with relevant neighborhood organizations to incorporate the Filipino Cultural Heritage District into the program of the development, including but not limited to, the proposed public art component. (source)
2020-004414CUA (2022)	<i>Market Octavia Affordable Housing Fee.</i> The Project is subject to the Market and Octavia Affordable Housing Fee, as applicable, pursuant to Planning Code Section 416. (source)

7 The conditions that set the clock

Four conditions define the entitlement’s maturity in the real-options frame: *Validity* (how long the approval lasts before a permit must issue), *Diligent Pursuit* (that construction, once permitted, continue), *Expiration and Renewal* (what happens when the permit lapses), and *Extension* (when the clock stops). Table 20 classes each condition by its heading — or, in the eras that print none, by the first words of its body — reads the first period its body states, and tabulates the periods by hearing year; Figure 3 shows the validity period year by year.

The result is simple. The validity condition states a period on 98% of the 3,915 motions that carry one, and the period is 36 months on 96% of those; the exceptions are shorter or longer periods set for particular projects. Diligent pursuit and expiration state the same period (Table 20). The extension condition carries no period at all on most motions: of 3,488 carrying one, 32 state a period. The modern text reads “All time limits in the preceding three paragraphs may be extended at the discretion of the Zoning Administrator where implementation of the project is delayed by a public agency, an appeal or a legal challenge and only by the length of time for which such public agency, appeal or challenge has caused delay.” **The option’s term is fixed by template, and its extension is state-contingent:** it lengthens exactly when the approval is litigated or held up by another agency.

Table 20: The conditions that set the entitlement’s clock, and the period each states, by hearing year. A condition is classed by its heading or, in the eras that print none, by the first words of its body; its period is the first the body states, in months. For each kind: the motions carrying it, the modal period, and the share of those stating a period that state the modal one. Years with fewer than 5 such motions are pooled.

Year	Validity			Diligent pursuit			Expiration and renewal			Extension		
	Motions	Modal	At modal	Motions	Modal	At modal	Motions	Modal	At modal	Motions	Modal	At modal
2001	5	18	40%							1	—	—
2007	5	36	80%	1	36	100%	1	36	100%	3	—	—
2008	18	36	94%							16	36	75%
2009	6	36	100%									
2010	163	36	93%				4	12	100%	17	36	100%
2011	259	36	98%							210	12	100%
2012	242	36	95%							209	12	100%
2013	305	36	93%	101	36	98%	103	36	96%	273	—	—
2014	207	36	97%	124	36	100%	125	36	100%	191	—	—
2015	108	36	96%	82	36	93%	79	36	95%	96	—	—
2016	163	36	98%	143	36	99%	141	36	99%	146	—	—
2017	160	36	99%	149	36	99%	150	36	100%	158	—	—
2018	284	36	98%	266	36	98%	269	36	98%	276	—	—
2019	335	36	97%	324	36	98%	331	36	97%	336	12	100%
2020	247	36	98%	235	36	100%	239	36	100%	247	—	—
2021	332	36	97%	323	36	100%	324	36	99%	330	18	100%
2022	182	36	100%	180	36	100%	180	36	100%	182	—	—
2023	343	36	94%	336	36	97%	338	36	94%	342	12	100%
2024	251	36	96%	200	36	100%	199	36	100%	204	24	100%
2025	215	36	98%	173	36	98%	174	36	100%	177	—	—
2026	49	36	86%	38	36	95%	38	36	95%	38	—	—
other years (fewer than 5)	7	36	43%							12	24	67%
undated	29	36	100%	15	36	100%	15	36	100%	24	—	—




Figure 3: The period the validity condition gives the sponsor to obtain a permit, by hearing year: the share of motions whose validity condition states fewer than, exactly, or more than the modal 36 months.

8 The conditions memo’s coding scheme on the full set

The conditions memo wrote a 13-category keyword scheme against the headings of the 225 packets its sample found. Table 21 runs it unchanged on the census. By distinct heading it reaches 48.7% of the 1,383 headings; weighted by how often each is imposed, 87.0%. On the eras that print no headings, where the scheme reads the body instead, it reaches 86.5% of bodies — a number that flatters it, because a body has more words for a keyword to hit. Weighted by imposition, 65.1% of headed conditions change the project’s obligations and 16.2% change the project. Table 22 lists the most frequent headings the scheme misses, the first of them First Source Hiring; Streetscape Plan; Transformer Vault; Overhead Wiring; Anti-Discriminatory Housing; Car Share.

The caveat stands. The keywords were written by reading the conditions memo’s packet headings and revised once against the headings the first draft missed; the coverage figures are in-sample to that extent. They support the claim that a small scheme spans most of what is imposed, not that the scheme is a validated classifier.

Table 21: The conditions memo’s thirteen-category scheme, run unchanged on the census. Headings are scored by distinct heading and weighted by how often each is imposed; the eras that print no headings are scored on the condition’s text instead, which the scheme was not written for. In-sample: the keywords were written against the headings of the first 225 packets, with one round of revision.

Family	Category	Headings, distinct	Headings, weighted	Unheaded bodies
Changes the project	Massing and envelope	4.0%	0.2%	12.0%
	Unit count and mix	1.5%	0.1%	3.8%
	Design and materials	8.0%	9.2%	18.5%
	Use and operations	5.8%	6.7%	18.9%
Changes its obligations	Affordability	3.9%	1.4%	2.8%
	Fees and exactions	6.0%	4.1%	7.3%
	Transport and parking	10.3%	11.7%	16.1%
	Open space and streetscape	4.8%	6.3%	7.9%
	Monitoring and reporting	4.8%	20.3%	23.9%
	Environmental mitigation	2.2%	1.6%	3.9%
	Historic preservation	0.5%	0.0%	2.9%
	Validity and timing	1.2%	21.0%	2.7%
Neither	Procedural and findings	2.1%	5.9%	28.9%
Any category		48.7%	87.0%	86.5%

Table 22: The most frequent headings the scheme does not reach.

Heading	Conditions
First Source Hiring	628
Streetscape Plan	462
Transformer Vault	336
Overhead Wiring	328
Anti-Discriminatory Housing	322
Car Share	298
Eating and Drinking Uses	287
Other Conditions	250
Transformer Vault Location	230
Duration	190
Art	185
Unit Mix	177
Showers and Clothes Lockers	174
Phasing	167
Number of Required Units	158

9 The numbers inside the conditions

The template’s words barely vary, and its figures do (§3). So the figures are read into typed columns rather than more prose parsed: `conditions_numeric.parquet` holds one row per canonical condition that states one of them — 6,970 conditions — with the motion section, case, hearing date and heading, each typed value, and beside each value the words it was read from, so any value can be checked against its sentence. Each field is read only from conditions of its own kind (by heading, or the body’s opening words where the era prints none), so a figure is never borrowed from a neighbouring subject. The fields: the validity period in months; the first operating-hours range a condition states (opening and closing hour, and whether it is daily, weekday or weekend); bicycle parking spaces by class; the parking maximum; the inclusionary share, the dwelling and affordable unit counts, and the income level the affordable-housing conditions state; screening dimensions; notice radii and notice periods; and monitoring or reporting intervals. When the stage was written 60 values drawn at random across the fields were read against their matched sentences and all were right; that is a check of the reading, not a validation of the coverage, and no field has been checked for conditions it missed.

Table 23 gives each field’s distribution and Figure 4 its median and interquartile band by hearing year. Three things stand out. The validity period is the template’s (3,871 conditions state one; §7). Operating hours are set for the site: 388 conditions state a range, and 31% of them let the premises close after midnight. And the affordable-housing conditions state the inclusionary share the project was held to — 351 of them, from 2010, most often 12% — which is the applied rate the exactions panel’s vesting rule should reproduce, an independent check on it. Screening dimensions are almost never stated (1 conditions); the other screening conditions are the wireless template’s, which state none.

The figures inside the conditions by hearing year: median and interquartile band; years with fewer than 10 conditions stating the field not drawn




Figure 4: The typed figures by hearing year: median (line) and interquartile band; years with fewer than 10 conditions stating a field are not drawn.

Table 23: The figures inside the conditions, typed: one row per field, over the canonical conditions that state it. ‘Conditions’ counts those carrying the field; the years are the first and last hearing year seen; the statistics are over the values. Hours are on a 24-hour clock, a closing time after midnight written past 24 (2 a.m. is 26).

Field	Conditions	Years	p10	Median	p90	Mean	Distinct	Most common
validity period (months)	3,871	1989–2026	36	36	36	35.9	9	36 (96%)
opening hour (24h)	388	2001–2026	6	7	11	7.8	21	6 (41%)
closing hour (24h; +24 past midnight)	388	2001–2026	19	22.5	26	22.9	19	22 (30%)
bicycle spaces, Class 1	978	2010–2026	0	2	83.6	24.1	116	0 (29%)
bicycle spaces, Class 2	978	2010–2026	0	0	10	5.1	39	0 (54%)
parking maximum (spaces)	464	2008–2026	2	9	157	51.6	95	2 (15%)
inclusionary share stated (dwelling units stated)	182	2011–2024	24.1	69	295.2	117.4	85	69 (5%)
affordable units stated	182	2011–2024	3	12	48.9	19.7	39	11 (9%)
income level stated (screening dimension (feet)	1	2019–2019	6	6	6	6	1	6 (100%)
notice radius (feet)	367	2008–2026	25	25	25	47.8	4	25 (91%)
notice period (days)	335	2008–2026	20	20	20	20	2	20 (100%)
monitoring or reporting interval (months)	499	2001–2026	12	24	24	20.6	6	24 (68%)

10 Recorded Notices of Special Restrictions

Every modern conditional-use motion carries a Recordation block requiring a Notice of Special Restrictions to be recorded against the parcel, stating the conditions; the notices would reach the conditions of cases whose motions are not online. Nothing was searched or downloaded to check this; the Assessor-Recorder’s public pages were read, and the terms below are quoted from them ([SF.gov](https://sf.gov), “[Get copies of recorded documents](#)”; the official-records site’s [disclaimer](#)). The index can be searched “by name, document number, document type, or by using the Assessor’s Parcel Number” and “does not allow searches by property address”; “online official record index information is available from January 1, 1990 forward”, and “documents recorded prior to January 1, 1990 can only be searched in our office”. A search returns an index entry. The image of a document is available to registered users, whose registration asks for identity verification, and is bought per document — online at a per-document price plus a card fee, or in person at a per-page price — at the rates the SF.gov page lists. The disclaimer says nothing about automated or bulk access, and the list of document types is not served to an anonymous session, so whether “Notice of Special Restrictions” is a selectable type could not be confirmed. **An index-only census of notices on the risk set’s parcels is possible in principle from 1990, one parcel at a time; the text costs a purchase per document; the pre-1990 notices are in the office only; and whether bulk index access is permitted is a question for the Recorder, which this job did not ask.**

11 Established, and not established

Established.

1. The case universe is 8,958 cases, defined once; the 8,987 in the earlier memos is printed strings, 29 of them the same case written two ways.
2. No directory lists the documents. The census found them by name: 10,165 documents among 127,920 URLs asked for, from exact links in the minutes, the agenda and hearing pages and the Wayback index, and from every case and motion number the item table records.

3. Condition text exists for 48.2% of conditioned items. It reaches back to items heard in 1999, but before 2010 it is thin, and the pre-2010 residual is documents that were not found anywhere, not documents that were found and misread. The conditions memo’s “no amount of work recovers condition content before 2010” was a claim about two URL patterns; the truth is “little”, not “none”.
4. The conditions are a template: a fixed apparatus of enforcement, revocation and clock, a selected set of operating and design conditions whose text is fixed and whose numbers are the project’s, and a thin tail written for the site.
5. The count of conditions per motion is not rising with the conditioning share.
6. The option’s term is fixed by template at 36 months, and its extension is contingent on delay by others.
7. The adopted conditions differ from the draft’s in 36% of pairs, often without the item table recording a modification; how much of that difference is the Commission’s rather than staff completing the draft is not established.

Not established.

1. The residual. The motions for most pre-2010 conditioned items are not online; whether the department holds them, and in what form, is a question for the department.
2. The recorded notices, which would reach the same cases from the other side; see §10.
3. A validated classifier. The scheme’s coverage is in-sample; the next step is a hand-coded set of conditions scored the way every other field is.
4. Whether the long tail predicts outcomes. It is quoted here, not yet coded.

12 Reproducing this

code/commission_minutes_processing/collect_conditions.py runs the census in stages, each cached and resumable; the parsing rules are in condition_parser.py.

```
python acquire_external_data.py sync      # materialise the Dropbox store
python collect_conditions.py discover    # listings, CDX, hearing and
                                         # agenda pages, minutes' links
python collect_conditions.py probe       # HEAD every candidate
python collect_conditions.py pull --host <host> --loop-minutes 15 \
    --max-mb 60                          # one process per host
python collect_conditions.py reextract --network
                                         # pages read before /Rotate fix
python collect_conditions.py parse       # one row per condition
python collect_conditions.py diff        # draft against adopted
python collect_conditions.py gold        # draw the gold set (once)
python collect_conditions.py freeze --round 1 # hash the rules
python collect_conditions.py score --round 1 # against gold_labels
python collect_conditions.py archive --round 1 # keep round 1
python collect_conditions.py freeze --round 2 # after revising
python collect_conditions.py score --round 2 # in-sample
python collect_conditions.py sample --round 2 # rows after the
```

```

# freeze (once), checked by hand
python collect_conditions.py score --round 2 # ...and out of sample
python collect_conditions.py archive --round 2 # keep round 2, whole
# parse included
python collect_conditions.py freeze --round 3 # after the merge fixes
python collect_conditions.py parse
python collect_conditions.py score --round 3 # in-sample, and
# round 2's rows carried
python collect_conditions.py pull --host <host> --max-mb 2000
# the rest of the pull

python collect_conditions.py parse
python collect_conditions.py sample --round 3 # out of sample (once)
python collect_conditions.py score --round 3
python collect_conditions.py summary # task1_summary.md
python collect_conditions.py numbers # conditions_numeric.parquet
python collect_conditions.py report # tables, figures, macros

```

Everything lands in `$MFHR_DATA_ROOT/external/cpc-packets/`: manifests/ (discovery), availability_full.csv (the census), docs/ (the motion sections kept, with their extracted lines), pull_log.csv (per-document wall time), conditions_long.parquet (and .csv) and motion_sections.csv (the parse), validation/ (the frozen round) and task1_summary.md. report regenerates tables/conditions_content_tables.tex, tables/conditions_content_macros.tex and the three figures. No number in this memo is hand-placed.

A Data dictionary for conditions_long

One row per condition: per (document, motion section, condition). Rows marked **canonical** are the one copy of each motion section the analysis uses; the rest are the same motion read from a mirror or an exhibit, kept so the choice can be audited.

Table 24: `conditions_long`: every column, with its share of rows populated (non-empty, or true for a flag) over all 94,169 rows, canonical or not.

Column	Filled	Meaning
<code>case_no</code>	100%	The case number the document prints (the running header's most frequent), normalised; empty where none is printed.
<code>case_key</code>	89%	The case in the reconciled universe the row belongs to (see <code>case_match</code>); empty where it does not resolve to exactly one.
<code>case_stem</code>	99%	<code>case_key</code> (else <code>case_no</code>) with its suffix letters removed, by the shared <code>case_stem</code> .
<code>motion_no</code>	42%	The motion or resolution number from the title line; empty for a draft.
<code>doc_type</code>	100%	<code>adopted_motion</code> or <code>draft_packet</code> (a title reading "Draft Motion" or a placeholder number, with no real number in the title).
<code>doc_url</code>	100%	The first URL the document was read from; the lines cache lists every URL that served the same bytes.
<code>hearing_date</code>	99%	ISO date from the "Hearing Date" line, else the date in a date-keyed URL, else the item table's date for the motion number.
<code>adoption_date</code>	41%	ISO date from "ADOPTED ... on jdatej"; empty for drafts.

Column	Filled	Meaning
<code>section_heading</code>	99%	The standing block the condition sits under (PERFORMANCE, MONITORING, ...; in 1998–2009 the lettered part, e.g. ‘The Approved Project’).
<code>condition_no</code>	71%	The printed number: 7, a letter C, or B(2) for a parenthesised item under lettered part B; empty for a named, unnumbered condition or a standing block.
<code>ordinal</code>	100%	Position of the row within its motion section, from 1.
<code>heading</code>	94%	The condition’s name: its bold lead-in, or a short Title Case run before the first full stop where the document has no fonts; empty where none is printed.
<code>body</code>	100%	The condition’s text with the heading, running headers, footers, page numbers and the compliance line removed; lines rejoined, hyphenation undone.
<code>compliance_contact</code>	66%	The “For information about compliance, contact ...” line(s) moved out of the body.
<code>page_start</code>	100%	Page of the source document (1-based, in the original file’s numbering) where the condition starts.
<code>page_end</code>	100%	Page where it ends.
<code>n_chars</code>	100%	Length of <code>body</code> .
<code>has_dollar</code>	0%	<code>body</code> contains a dollar figure.
<code>has_percent</code>	2%	<code>body</code> contains a percentage.
<code>has_numeric_quantity</code>	19%	<code>body</code> contains a figure with a unit (units, feet, spaces, hours, days, months, years, a.m./p.m., seats, ...).
<code>code_sections_cited</code>	24%	Planning Code sections cited, as printed, semicolon-separated.
<code>code_sections_norm</code>	24%	The same with the Article 4 recodification applied (§315 → §415 and the other pairs the motions themselves state as “formerly”).
<code>parse_method</code>	100%	How the start was found: <code>numbered</code> , <code>numbered+bold</code> , <code>numbered+text</code> , <code>bold_heading</code> , <code>lettered</code> , <code>paren</code> , <code>section_block</code> ; <code>+ocr</code> when the page was OCR’d, <code>+ocrdigit</code> when an OCR-misread number was repaired.
<code>parse_confidence</code>	100%	<code>high</code> , <code>medium</code> or <code>low</code> , by rule: low for an implausible length or an unheaded OCR row outside a numbered list; medium for OCR, implicit blocks, sequence gaps and text-read headings.
<code>part</code>	100%	<code>preamble</code> for the standing blocks before the “Conditions of Approval, Compliance, Monitoring, and Reporting” line; <code>conditions</code> otherwise.
<code>implicit</code>	24%	The row is a standing block with prose and no condition start (AUTHORIZATION, SEVERABILITY).
<code>sequence_gap</code>	1%	The number skips one or two from the expected sequence.
<code>style</code>	100%	The section’s numbering style: <code>numbered</code> , <code>bold_heading</code> , <code>paren</code> , <code>lettered</code> , <code>unknown</code> .
<code>container</code>	100%	<code>motion</code> (an adopted-motion file), <code>packet</code> , or <code>html</code> (a pre-2003 motion page).
<code>embedded_in_packet</code>	7%	An adopted motion that is not the file’s own: attached to a packet, or to a later motion that modifies it.
<code>instrument</code>	100%	<code>motion</code> or <code>resolution</code> .
<code>case_match</code>	100%	How <code>case_key</code> was reached: <code>exact</code> , <code>serial padded</code> , <code>expanded</code> (two-digit year), <code>stem</code> (the only case with that stem), <code>motion number</code> (the item table’s case for the motion), or why not.
<code>canonical</code>	92%	The one copy of this motion section the analysis uses: a standalone file over an embedded copy, a text layer over OCR, then the fuller parse.

Column	Filled	Meaning
<code>doc_id</code>	100%	First 16 hex digits of the document's SHA-256; names its cache files.
<code>section</code>	100%	Index of the motion section within the document, from 0.